



# **Toronto Transit Commission** **Signage and Wayfinding Standards**



**Toronto Transit Commission**  
**Signage and Wayfinding Standards**

**June 2021**







## Contents

1.0	Introduction	1.6
2.0	Planning principles	2.1
3.1	Graphic elements	3.2
3.2	TTC logo	3.3
3.3	Typography	3.4
3.4	Colour	3.6
3.5	Arrows	3.10
3.6	Line numbering	3.12
3.7	Route numbering	3.14
3.8	Logos	3.22
3.9	Pictograms	3.31
3.10	Text modules	3.67
4.1	Insignia Pylon	4.2
4.2	Station entrances	4.16
4.3	Station information	4.32
4.4	Station fareline	4.52
4.5	Surface route platform	4.56
4.6	Directional	4.68
4.7	Elevator	4.84
4.8	Station platform	4.106
4.9	Station	4.110
4.10	Maps	4.132
4.11	Track level signage	4.134
4.12	Street level signage	4.148
4.13	Safety and security	4.150
4.14	Back of house	4.160
4.15	Front of house	4.168

## 1.0 Introduction

The objectives of these *Signage and Wayfinding Standards* are to provide direction and guidance to staff and third party contractors for the development of effective wayfinding within TTC facilities.

More specifically, it is designed with the following key objectives in mind:

- to support the TTC's Customer Information Strategy initiative – information customers need, when they need it;
- to facilitate optimal access to transit services for all customers regardless of impairment: mobility, cognitive abilities or language;
- to present a uniform sign system that communicates information effectively and efficiently;
- to ensure that wayfinding elements, such as signs, function within the context of their environment and do not detract from the customer experience;
- to promote best practices in the field of transit wayfinding and information design;
- to maintain high standards for customer care, consistent with the TTC's rich tradition of safety, service and courtesy.

These standards have been approved by the Toronto Transit Commission's Executive Board. All new TTC signs must conform to these standards.

The success of these standards can only be measured by the extent of their correct implementation, and it relies heavily on those who coordinate signage within each of the TTC's departments, partner agencies and third party contractors.





## **2.0 Planning principles**

## 2.0 Planning principles

### Introduction

The *Signage and Wayfinding Standards* contain a variety of guidelines, tools, and resources that will assist qualified design professionals to develop signage for TTC facilities. This section seeks to provide guidance on a general wayfinding strategy and specific rules applied to signage at the TTC.

The following planning principals should be reviewed prior to developing signage plans.

### Meet the basic objectives of wayfinding

The basic objectives of wayfinding signage are to provide customers with self-navigation tools that will allow them to know:

- Where they are;
- Where their destination is;
- The best route to reach their destination;
- That they have arrived at their destination;
- How to find their way back to where they started.

In addition to wayfinding, signs are used to address other equally important objectives:

- Provide safety information;
- Post prohibitive instructions;
- Identify accessible pathways, devices, and services;

Meeting these objectives should guide decisions made on the types of signs used, message content, and placement locations.

### Providing answers

There are a number of elements within the TTC system that work in concert together to provide customers' wayfinding needs. Thus it is important to understand that wayfinding elements must complement one another using consistent terminology, editorial style, tone, look and feel.

### Proximity – Where am I?

Our customers must have a sense of their proximity at all times. Customers who know where they are become less likely to feel 'lost' and become more confident and empowered. Understanding proximity at points along a journey also contributes to an understanding of progress and an estimation of arrival at final destinations.

Our system provides a number of tools customers can access to keep track of where they are:

- 'You are here' markers on TTC System Maps;
- Station name signs at entrances and platform walls;
- Bus shelter street name identification;
- Visual and audible station/stop announcements.

Our customers perceive the transit system as a large and complex environment. They rely on correct signing and information to make informed decisions for navigating through the system efficiently and safely.

The TTC Wayfinding System incorporates visual coherence, clarity, and simplicity for all elements.

A simple, clear and concise hierarchy of signing ensures easy to follow directions for customers including:

- Clear, legible and visible statements;
- Safe and effective use of the transit system;
- A unifying brand identity;
- Flexibility;
- Accessibility and inclusiveness for all users;
- Maintainability;
- and cost effectiveness.

The TTC sign system incorporates a number of elements that together ensure these objectives are met:

- High contrast design elements;
- Pictograms;
- Prominent directional arrows;
- Modular layout structure;
- Numeric and colour coding system.

Sign placement is determined based on the idea of establishing a unified progression of messages leading customers along their journeys. Sign placement generally occurs at the following points:

### 1. Arrival points

Arrival points are the locations that customers first arrive on a TTC property, usually subway stations or surface route stops. They could also be a point where customers are arriving from a connecting partner transit system like GO Transit

## 2. Informational points

These include *Plan your trip* information stations (with system maps and vicinity maps), Route connections (surface route platform map and route listings), Next Vehicle Arrival Screens (NVAS), Station Information Screens (SIS) and Station Hubs. Informational points are generally where customers can identify where they are, where they want to go and the best route to take in order to get there.

## 3. Decision points

Is a general term use to identify any point where customers have options or choices. Signs are required at decision points in order for customers to make informed decisions

## 4. Destinations

Destinations include both final destination and intermediate destination. A final destination may be a station on a subway line or stop along a bus route. Intermediate destinations may be a particular point in the journey that a customer needs to reach in order to proceed to the next stage of their journey. Signs posted at destinations inform customers that they have arrived or reached a key point along their journey.

### Anticipate multi-modal journeys

Typical journeys for TTC customers involve several stages, using different modalities. These may include riding a bus, transferring to a subway, and completing their journey on a streetcar. These journeys are multi-modal, meaning that they will probably utilize a combination of methods and vehicles to complete a single journey. Customers plan these journeys by visualizing linear routes comprised of a sequence of steps. They use wayfinding information as a tool to piece journey plans together. Therefore, it is crucial that different modal systems, such as subways and streetcars, 'fit' together. Users need to be able to easily understand where and how they move from one point of their journey to another. Often, there are different route options to reach a single destination. Wayfinding information must illustrate differences, such as distance and time, clearly so that customers can make informed decisions about the best way to plan their journeys.

### Intermodal stations

As we support our growing region, the operators of each agency play a part to assist customers across the region. Intermodal stations are stations with transfers between two or more operators. Our system pairs the operator logo with the modality for customers to navigate to the services they require. For example, Kipling station has MiWay buses, TTC buses and GO buses as well as a GO train and TTC Line 2. It is important to pair the logo with the modality as the buses are located in different bus terminals at Kipling station. Refer to the *TTC Intermodal Wayfinding and Signage standards* manual for more information.



### Interchange stations

A transfer between two TTC subway lines is an interchange station. At interchange stations the terminus stations become important to support the line numbers. For example, Kennedy station is the terminus for Line 2, Line 3 and Line 5. When customers are trip planning at this station the line numbers are more clear when they are paired with their terminus: Line 2 Kipling, Line 3 McCowan and Line 5 Mount Dennis. At Bloor-Yonge, the station intersects two lines going all directions. Line 1 Finch / Vaughan via Union and Line 2 Kennedy / Kipling.



## 2.0 Planning principles

### Microtransit at stations

Microtransit means using private modes of transit to provide on-demand service; it can be one way of helping customers bridge the first and last mile of their trip.

Microtransit pictogram modules should not be used on station pylons or station identification signs. Where appropriate, a stop marker sign may be installed outside a station with the microtransit pictogram module.

Where microtransit is present outside a station, directional signage inside the station should include the microtransit pictogram module. The name of the service may be used to describe the pictogram (example: IKEA shuttle bus, bike share, etc.)



### Taxi stand and bike lockers

Taxi stand and bike locker pictograms should only be used on the egress exit sign closest to the taxi stand and bike locker.

### Be predictable

Stress and anxiety for customers is reduced when they can anticipate where they can find information and it is presented in a familiar manner. Consistent placement and graphic presentation contribute to this predictability.

Universal design principles for accessibility also contribute to predictability. Information presented in a familiar manner, such as universally understood pictograms, make signs easier for customers to understand. They remove steps required to learn the sign system. This is especially important for our customers who are visitors to the city and may face language barriers.

Once a customer understands how an information system works they are more likely to be confident and comfortable as their journey takes them through unfamiliar places within the system. These familiar markers will serve as assurance that they are on the correct path.

TTC pictograms follow industry best practices for symbol design. For instance, a bus pictogram used

on the TTC would match the pictograms used for many other transit operators. Using pictograms that new users are already familiar with contributes to the ease of use and better understanding of signs.



### Present information on different cognitive levels

Using a combination of words, colours, symbols and numeric codes to represent messages allows customers to interpret information in different cognitive ways.

These differences support the broad spectrum of customers riding the TTC. For instance, some customers have language barriers and only understand simple English; some customers are rushed and have short attention spans that make complex messages difficult to grasp; some customers are colour-blind and others may have cognitive limitations. For these reasons, it is useful to present information simultaneously on several sensory and cognitive levels.

Messages can be presented all together at once or in parts depending on how customers need the information. For instance, numeric codes provides customers with a shorthand method of identifying routes. These codes, once understood, allow customers to quickly identify TTC bus, streetcar and subway routes. These codes also facilitate future technologies. For instance, smart phone apps can be used more efficiently when users can input short numeric codes rather than long route names.



Colours on maps make linear routes easy to understand, providing clear separation and geographic reference points.

### Progressively disclose information

Messages that are clear and simple are more easily understood and memorable. However, often there are multiple messages that customers must receive and understand along their journeys. These messages may range from general information down



to specific detail. Releasing information sequentially in small amounts at predictable intervals prevents customers from being overwhelmed with too much information all at once.

This section provides guidelines on what information should be placed on signage at specific points within subway stations. Messages are designed to address two specific types of journeys; ingress and egress. Though signs will be positioned throughout the station, they may be grouped corresponding to station areas.

### Keep destination names simple and consistent

Naming principles apply equally to all modes and facility types; stations, routes and stops. There are three core principles to all naming for wayfinding information. Names should be simple, logical and permanent.

Simple names are more memorable and easier to use in the course of everyday conversation when giving directions. Anticipating how the public may simplify a place name, can lead to better adoption. For instance, naming a station Royal Ontario Museum though more descriptive, is not as expedient as simply calling it Museum. Short names are also easier to commit to memory.

An example of simplification of a station name is Vaughan Metropolitan Centre. Wayfinding signage refers to the terminus as 'Vaughan'. The full station name appears on maps, trip planning and web applications. 'Vaughan' is used on directional signage, 'You are Here' maps and other signage referring to the terminus.

Logical names assist customers in planning their journeys. Names should be connected in some manner to their geographic location. Names should also provide customers with proximity. Presently, within the system stops, routes and stations are named after; a nearby street, a large civic centre, a neighbourhood, or a historic landmark.

Names should stand the test of time. Care should be taken not to adopt a name that could easily change in the future.

Consistency in naming is important. Generally, words like 'Avenue' and 'Road' should be spelled out in full. Abbreviations are discouraged and should only be used when absolutely necessary,

for instance, when space is limited.

When referring to street names such as Bloor Street West and King Street West, remove the direction from the street name. When there are multiple exits to the same street, these cardinal directions may be used to orient customers.

Example: St Andrew Station

#### Northeast corner

King Street, East side  
University Avenue, North side

#### Southeast corner

King Street, East side  
University Avenue, South side

#### Northwest corner

King Street, West side  
University Avenue, North side

#### Southwest corner

King Street, West side  
University Avenue, South side



### Present messages on signs as lists (not sentences)

Removing extraneous words such as 'and' and 'to' make messages simpler and faster to read.

Destination messages on signs should be presented as lists rather than strung together as sentences. Place destinations on different text lines or use a comma. Ampersands are not used on signage. When referencing two terminus together on the same line a '/' is used between the two terminus.

Example: Kennedy / Kipling.



## 2.0 Planning principles

### Incorporate accessibility planning

The International Symbol of Access (ISA) is used to identify accessible pathways and services within the TTC system.



### Barrier-free path of travel (accessible pathway)

A barrier-free path of travel provides an unobstructed path of travel within the transit facility for persons with physical or sensory disabilities and others with mobility issues. This pathway may include ramps, passenger elevators or other platform equipped passenger elevating devices.

### Accessible transit services plan

The TTC is committed to making its services accessible in order to better meet the needs of seniors and people with disabilities in the City of Toronto, and has a systematic program in place to ensure that this is accomplished in a cost-effective and timely manner.

The Commission also subscribes to the *City of Toronto Accessibility Design Guidelines*.

### Identification of barrier-free entrances and exits

All transit facility entrances that are barrier-free are to be signed with the International Symbol of Access (ISA). In the event that only one entrance to the facility is accessible, an accessible pathway using the ISA symbol should be signed to the closest accessible entrance.

### Identification of barrier-free path of travel

When the barrier-free path of travel deviates from the normal path of travel, the International Symbol of Access (ISA) is used to identify the accessible pathway.

### Identification of barrier-free devices

When the barrier-free path of travel includes the use of an accessible device (e.g. ramp or elevator), the device is identified along the barrier-free path of travel at the immediate location of the accessible device. This is to done specifically to inform users of a change in the barrier-free path of travel prior to their arrival at the device.

### Identify where elevators lead to

In many TTC stations several elevators provide passage between street level and subway platforms. Customers may need to use one elevator to reach a concourse level and then choose between one of two elevators that lead down to different platforms and levels. Therefore, it is crucial that signage identifying elevators includes destination information so that customers can identify the correct elevator.

### Non-accessible entrances

At accessible stations, non accessible entrances require redirect signage to the nearest accessible entrance. This is an AODA requirement.

Example:

Accessible entrance on other side of St Clair Avenue  
Accessible entrance at north side of station



### Second exits

All entrances to the station show the modalities available at the station. For second exits, additional signage is required on the pathway to let customers know they need to use the platform to transfer to other modalities.

### Streetcar / bus platforms

Station identification is not required on platforms. The focus should be placed on wayfinding to other modalities at the station.



### Stair and escalator directional

When a platform has a stair / escalator combination, the sign pointing into the path only shows an escalator.

A diagonal arrow is only used for a wall mounted sign beside a staircase or escalator.



### Suspended sign

Content on any suspended sign with forward or down arrow is centered and nudges customers to the appropriate side of the pathway.



### Design signs to last

Signs within the transit system are designed for long service life in all aspects. Typically, the minimum life expectancy should be ten years. Though there are many examples throughout the system of signage that is as old as the system and still provide vital wayfinding information to our customers.

Signs that are within reach of customers (any sign within 2400 mm above finished floor) are exposed to possible damage from tampering and vandalism. The materials and fabrication methods chosen should take into account the likelihood that signs may receive hammer blows, felt markers, scratching, burning, spray paint, etc.

Signs should be corrosion resistant. Where there is potential for electrochemical corrosion between metals, protective coating films, sealants or insulating membranes shall be applied. Examples include;


- Aluminum to stainless steel, brass, bronze, copper, zinc;
- Stainless steel to brass, bronze, copper, zinc;
- and metals to concrete or masonry.

Additionally, signs should be resistant to environmental factors that may dislodge them. For instance, vibrations, wind pressure, severe temperature change and the rigours of regular cleaning. Refer to Design Manual 0301-02 environmental loads for more information.

This manual details standard materials use for each sign type in section 4.0 Sign typology.

### Sequence of information presentation

Consistent sequencing contributes to simplicity and readability. For example, pictograms are always positioned in a hierarchical sequence. The diagram below illustrates the proper sequence of graphic elements on typical TTC signs.





**3.0 Graphic elements**  
**Table of contents**

3.1	Graphic elements	3.2
3.2	TTC logo	3.3
3.3	Typography	3.4
3.4	Colour	3.6
3.5	Arrows	3.10
3.6	Line numbering	3.12
3.7	Route numbering	3.14
3.8	Logos	3.22
3.9	Pictograms	3.31
3.10	Text modules	3.67

## 3.1 Graphic elements

TTC signs are created by combining a number of components, such as: standardized layout grids, corporate fonts, logos, symbols and frames. We refer to these components as 'Graphic elements'.

This section of the Standards seeks to explain what these elements are, how they are designed and how they are used to create signs. Generally, these elements should be considered 'standard' meaning that they have been approved for use within the TTC's sign system and therefore should not be altered or replaced unless approved.




## 3.2 TTC logo

### 3.2.1 The TTC Logo

Consistent application of the TTC logo is vital to maintaining consistent corporate identity for the TTC. TTC logos are included on signage at points of entry into the system; that is, at points when customers access the system, station entrances, bus and streetcar stops, and vehicles.

### 3.2.2 Backgrounds

The TTC Logo appears against white and black backgrounds on TTC signage. Note that when positioned against a background other than white, a white outline appears around the logo. This outline is included within the official logo files.



## 3.3 Typography

### 3.3.1 – Swiss 721 BT

The primary typeface for TTC signage is Swiss 721 BT. It is a highly readable sans serif font. The design of individual letters complies with proportional requirements for the Access for Ontarians with Disabilities Act (AODA). Swiss 721 BT is used in six weights; Light, Regular, Medium and Bold. Swiss 721 is a Bitstream (BT) font available at [www.myfont.com](http://www.myfont.com).

The integrity of the font should be maintained at all times. No vertical or horizontal scaling, no added stroke, etc. To ensure consistency, always use Swiss 721 and not Arial or a substitute font.

Due to licensing restrictions, TTC is unable to provide copies of this typeface.

### 3.3.2 – Bloor-Yonge

Swiss 721 is used for most wayfinding signage. However, exceptions occur on several sign types that refer to station and streetcar stops. In these instances the Bloor-Yonge font is used. Bloor-Yonge is available for free download from TTC Design and Wayfinding ([wayfinding@ttc.ca](mailto:wayfinding@ttc.ca)). The Bloor-Yonge font consists of upper case letters, numerals and several punctuation symbols.

Swiss 721 BT Light

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
 OPQRSTUVWXYZ  
 abcdefghijklmn  
 opqrstuvwxyz  
 1234567890.,:;&

Swiss 721 BT Regular

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
 OPQRSTUVWXYZ  
 abcdefghijklmn  
 opqrstuvwxyz  
 1234567890.,:;&

Swiss 721 BT Medium

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
 OPQRSTUVWXYZ  
 abcdefghijklmn  
 opqrstuvwxyz  
 1234567890.,:;&

Swiss 721 BT Bold

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
 OPQRSTUVWXYZ  
 abcdefghijklmn  
 opqrstuvwxyz  
 1234567890.,:;&



## Typography

Swiss 721 BT Heavy

**ABCDEFGHIJKLMN  
OPQRSTUVWXYZ  
abcdefghijklmn  
opqrstuvwxyz  
1234567890.,:;&**

Swiss 721 BT Bold Condensed

**ABCDEFGHIJKLMN  
OPQRSTUVWXYZ  
abcdefghijklmn  
opqrstuvwxyz  
1234567890.,:;&**

Bloor-Yonge Regular

**A B C D E F G H I J  
K L N O P Q R S T U  
V W X Y Z - '  
1 2 3 4 5 6 7 8 9**

## 3.4 Colour








### Primary colour palette

Primary colours are used to identify major elements within the system such as subway lines, exits and accessible features. Each has been named after the element that it is most closely associated with.

Colours are specified using different colour matching systems depending on the method of fabrication. Generally, better quality and consistency is achieved when TTC designers specify exactly which colour is desired using an applicable colour matching standard rather than relying on fabricators

to interpret TTC requirements based on a 'close' match. Therefore, each colour can be identified several ways depending on the application. For example, when printing digitally, Line 1 Yellow should be identified as C0 M20 Y100 K0. When using 3M vinyl products, it should be identified as 3M 3620-25 – Sunflower.

The colour table shows all the typical colour matching systems used for TTC signage.

	Colour Name	Applications	PANTONE	CMYK	RGB	3M Translucent	3M Opaque	3M Reflective	Gerber Foil	Matthews Paint
	Line 1 Yellow	Line 1	123	C 0 M 20 Y 100 K 0	R 248 G 195 B 0	3630-25 Sunflower	-	-	GCS-625 Sunflower Yellow	49 MP08967 New Holland Yellow LRV 49.4
	Line 2 Green	Line 2   Affirmative Pictograms   Express Routes	347	C 100 M 0 Y 100 K 0	R 0 G 146 B 63	3630-146 Light Kelly Green	-	680-77 Green	GCS-46 Kelly Green	167 MP00448 Greenward LRV 25.2
	Line 3 Blue	Line 3   Accessibility	2194	C 100 M 15 Y 0 K 0	R 0 G 130 B 201	3630-57 Olympic Blue	3650-57 Olympic Blue	680-76 Light Blue	GCS-57 Olympic Blue	39 MP00973 Diner Door Blue LRV 15.6
	Line 4 Purple	Line 4	234	C 10 M 100 Y 0 K 20	R 162 G 26 B 104	3630-133 Raspberry	-	-	GCS-133 Raspberry	178 MP14926 Ruby Dee LRV 11.3
	Line 5 Orange	Line 5   Temporary Wayfinding and Signage Shuttle Stops   Path Logo "A"   Train Stop Marker	Orange 021	C 0 M 60 Y 100 K 0	R 235 G 135 B 56	3630-44 Orange	3650-14 Bright Orange	680-14 Orange	GCS-14 Orange	100 MP00170 Moline Orange LRV 26.6
	Line 6 Grey	Line 6   General Use Grey Scale Fill	423	C 0 M 0 Y 0 K 50	R 150 G 149 B 148	3630-51 Silver Grey	3650-31 Medium Grey	-	GCS-31 Grey	50 MP06388 Battleship LRV 39.4
	Line 7 Mint	Line 7	352	C 35 M 0 Y 45 K 0	R 139 G 202 B 152	-	-	-	-	127 MP01662 Sunlit Glade LRV 59.9







## Colour

	Colour Name	Applications	PANTONE	CMYK	RGB	3M Translucent	3M Opaque	3M Reflective	Gerber Foil	Matthews Paint
	TTC Red	Local Routes TTC Logo   Exit Module Regulatory Signs   Path Logo "P"	485	C 0 M 100 Y 100 K 0	R 218 G 37 B 29	3630-43 Light Tomato Red	3650-13 Tomato Red	680-72 Red	GCS-13 Tomato Red	8 MP15024 Red Dragon LRV 15.7
	Safety Yellow	Safety & Security Regulatory Emergency Trip Location Cross Passage Logo Path "H"	109	C 0 M 0 Y 100 K 0	R 255 G 245 B 0	3630-015 Yellow	3650-15 Bright Yellow	680-81 Lemon Yellow	GCS-15 Yellow	40 MP10211 Citrus Yellow LRV 61.6
	Male Staff Blue	Staff Washroom ID	2985	C 70 M 0 Y 0 K 0	R 0 G 168 B 230	-	3650-77 Peacock Blue	-	GCS-77 Peacock Blue	52 MP00344 Baby Boy Blue LRV 44.9
	Female Staff Pink	Staff Washroom ID	224	C 0 M 70 Y 0 K 0	R 232 G 103 B 156	-	3650-103 Magenta	-	GCS-643 Pink	171 MP00089 Pink Panther LRV 32.4
	Janitor Purple	Janitor ID	-	C 40 M 40 Y 0 K 0	R 155 G 149 B 201	-	-	-	-	-
	Safety Partner Blue	Safety Partner Logo   Notice background   Blue Night Routes	Reflex Blue	C 100 M 75 Y 0 K 0	R 2 G 65 B 130	3630-157 Sultan Blue	-	-	GCS-37 Cobalt Blue	38 MP02110 Cook Islands Blue LRV 8.4
	Safety Partner Green	Safety Partner Logo	-	C 100 M 0 Y 45 K 10	R 0 G 147 B 120	3630-146 Light Kelly Green	-	-	GCS-176 Aqua	167 MP00448 Greenward LRV 25.2
	Safety Instructions Green	Safety Instructions Background	3288	C 100 M 0 Y 75 K 15	R 0 G 127 B 94	3630-116 Bright Jade Green	-	-	GCS-46 Kelly Green	168 MP01669 Emerald Sea LRV 20.2
	Train Stop Green	Train Stop Marker Guard's Position Located adjacent to 5th Car   Emergency Trip Location Identification	369	C 60 M 0 Y 100 K 0	R 56 G 172 B 54	-	3650-196 Apple Green	-	GCS-196 Apple Green	76 MP13551 Nick Green Slime LRV 39.4
	Train Stop Red	Train Stop Marker Operator's Position Located adjacent to Front Car	1805	C 0 M 100 Y 100 K 20	R 171 G 56 B 29	-	3650-63 Geranium	-	GCS-53 Ruby Red	1 MP10224 Hotrod Red LRV 12

## Colour

	Colour Name	Other Applications	PANTONE	CMYK	RGB	3M Translucent	3M Opaque	3M Reflective	Gerber Foil	Matthews Paint
	Black	Background Fill Text Fill General Use Grey Scale Fill / UP Express	Black	C 0 M 0 Y 0 K 100	R 31 G 28 B 23	3630-22 Black	3650-12 Black	680-85 Black	GCS-12 Black	16 MP59647 Black is Black LRV 4.4
	Dark grey	General Use Grey Scale Fill   Community Bus Routes	425	C 0 M 0 Y 0 K 70	R 96 G 93 B 92	3630-61 Slate Grey	3650-41 Dark Grey	-	GCS-151 Traffic Grey	63 MP03730 Metalshop Grey LRV 13.4
	Light grey	General Use Grey Scale Fill	420	C 0 M 0 Y 0 K 10	R 222 G 222 B 221	-	-	-	GCS-681 Light Grey	49 MP07273 Graytint LRV 66.4
	White	Background Fill Text Fill General Use Grey Scale Fill	-	C 0 M 0 Y 0 K 0	R 255 G 255 B 255	3630-20 White	3650-20 White	680-10 White	GCS-10 White	1 MP32071 White Wonder LRV 89.5
	Rich black	Special Use Ultra Black CMYK Process Printing Colour	Black C	C 60 M 40 Y 40 K 100	R 10 G 11 B 12	-	-	-	-	-
	PRESTO Green	PRESTO	366	C 29 M 0 Y 64 K 0	R 183 G 221 B 121	-	-	-	-	-
	YRT Blue	York Region Transit logo	300	C 100 M 44 Y 0 K 0	R 0 G 121 B 193	3630-127 Intense Blue	-	-	GCS-47 Intense Blue	24 MP11430 Alhambra Mosaic Blue LRV 10.1
	VIVA Blue	VIVA Blue route lozenge	299	C 85 M 19 Y 0 K 0	R 0 G 157 B 220	3630-147 Light European Blue	-	-	GCS-57 Olympic Blue	39 MP00973 Diner Door Blue LRV 15.6
	VIVA Melon	VIVA Melon route lozenge	232	C 3 M 83 Y 0 K 0	R 231 G 82 B 157	-	-	-	-	-
	VIVA Plum	VIVA Plum route lozenge	2592	C 76 M 0 Y 6 K 0	R 149 G 97 B 168	-	-	-	-	-
	VIVA Kiwi	VIVA Kiwi route lozenge	382	C 29 M 0 Y 100 K 0	R 193 G 216 B 47	-	-	-	-	-

## Colour

	Colour Name	Other Applications	PANTONE	CMYK	RGB	3M Translucent	3M Opaque	3M Reflective	Gerber Foil	Matthews Paint
	VIVA Tangerine	VIVA Tangerine route lozenge	306	C 0 M 35 Y 90 K 0	R 251 G 176 B 52	-	-	-	-	-
	GO Transit	GO logo	370	C 49 M 0 Y 100 K 30	R 101 G 141 B 27	-	-	-	-	-
	VIA	VIA logo	-	C 2 M 24 Y 91 K 0	R 248 G 194 B 50	-	-	-	-	-
	Züm	Züm logo	-	C 4 M 91 Y 78 K 0	R 230 G 62 B 65	-	-	-	-	-
	MiWay	MiWay logo	-	C 0 M 76 Y 100 K 0	R 242 G 99 B 34	-	-	-	-	-
	DRT Pulse	DRT Pulse logo	-	C 7 M 72 Y 100 K 1	R 224 G 104 B 37	-	-	-	-	-
	Durham Transit	Durham Transit logo	-	C 0 M 0 Y 0 K 100	R 0 G 112 B 60	-	-	-	-	-
	Bike Share Toronto	Bike Share Toronto logo	342	C 96 M 34 Y 81 K 27	R 0 G 101 B 72	-	-	-	-	-



## 3.5 Arrows

Arrows are used throughout the system to direct passengers. The shape and size of arrows is controlled by utilization of arrow modules that ensure consistent appearance in all applications.


### Arrow placement

Arrows indicating direction to the left should be placed on the left.

Arrows indicating direction to the right should be placed at the right.



Arrows



G-01-A024  
Straight Left Diagonal  
Down Turn



G-01-A025  
Straight Right  
Diagonal Down Turn



G-01-A026  
Straight Left  
Diagonal Up Turn



G-01-A027  
Straight Right  
Diagonal Up Turn



G-01-A101  
Diagonal  
Lower Left



G-01-A102  
Diagonal  
Lower Right



G-01-A103  
Diagonal  
Upper Left



G-01-A104  
Diagonal  
Upper Right



G-01-A105  
Down  
Straight Ahead



G-01-A106  
Left



G-01-A107  
Right



G-01-A108  
Up  
Straight Ahead

### 3.6 Line numbering

The TTC uses numeric codes along with street/destination names to identify bus, streetcar and subway line/routes. Letters are appended to identify route variations.

Numeric line/route codes offer several advantages;

- More accessible to customers with language or cognitive barriers;
- Provide a mnemonic reference that is easy for customers to remember;

- More conducive for integration with mobile technologies;
- Consistent with principals of universal design.

Numbers are typically assigned to routes by TTC Service Planning based on the order that routes go into service.

Subway lines are also identified with coloured circles as a secondary distinctive element.





Line numbering



G-02-A301  
Line 1 X



G-02-A102  
Line 1 Check



G-02-A103  
Line 2 X



G-02-A104  
Line 2 Check



G-02-A105  
Line 3 X



G-02-A101  
Line 3 Check



G-02-A102  
Line 4 X



G-02-A103  
Line 4 Check



G-02-A104  
Line 5 X



G-02-A105  
Line 5 Check



G-02-A101  
Line 6 X



G-02-A102  
Line 6 Check

### 3.7 Route numbering

#### Stop markers



G-08-A001  
Route\_Regular



G-08-A002  
Route\_Regular\_Limited



G-08-A003  
Route\_Express



G-08-A005  
Route\_BlueNight



G-08-A006  
Route\_BlueNight\_Branch



G-08-A007  
Route\_Community



G-08-A101  
Route\_Regular\_North



G-08-A102  
Route\_Regular\_South



G-08-A103  
Route\_Regular\_East



G-08-A104  
Route\_Regular\_West



G-08-A105  
Route\_Limited\_North



G-08-A106  
Route\_Limited\_South



G-08-A107  
Route\_Limited\_East



G-08-A108  
Route\_Limited\_West



G-08-A109  
Route\_Night\_North



G-08-A110  
Route\_Night\_South



G-08-A111  
Route\_Night\_East



G-08-A112  
Route\_Night\_West



G-08-A201  
Header\_TempStop



G-08-A202  
Header\_BlueNight



G-08-A202  
Header\_BlueNight



G-08-A204  
Header\_Community

Stop markers



G-08-A401  
Blue\_Night\_Badge



G-08-A402  
Express\_Badge



G-08-A403  
Community\_Badge



G-08-A501  
Shuttle\_Line-1-N



G-08-A502  
Shuttle\_Line-1-S



G-08-A503  
Shuttle\_Line-2-E



G-08-A504  
Shuttle\_Line-2-W



G-08-A505  
Shuttle\_Line-3-E



G-08-A506  
Shuttle\_Line-3-W



G-08-A507  
Shuttle\_Line-4-E



G-08-A508  
Shuttle\_Line-4-W



G-08-A601  
WheelTrans



G-08-A701  
Bands\_RoundHead



G-08-A702  
Bands\_Kydex



G-08-A703  
TTC\_Logo\_Decal



G-08-A704  
AccessStop\_Decal



G-08-A705  
NoAccessStop\_Decal

### 3.7 Route numbering

#### Bus bay ID – Suspended



G-08-B001  
Route\_Regular-LG



G-08-B002  
Route\_Reg\_North-LG



G-08-B003  
Route\_Reg\_South-LG



G-08-B004  
Route\_Reg\_East-LG



G-08-B005  
Route\_Reg\_West-LG



G-08-B006  
Route\_Regular\_Limited-LG



G-08-B007  
Route\_Reg\_Ltd\_North-LG



G-08-B008  
Route\_Reg\_Ltd\_South-LG



G-08-B009  
Route\_Reg\_Ltd\_East-LG



G-08-B010  
Route\_Reg\_Ltd\_West-LG



G-08-B011  
Route\_Express-LG



G-08-B012  
Route\_Express\_North-LG



G-08-B013  
Route\_Express\_South-LG



G-08-B014  
Route\_Express\_East-LG



G-08-B015  
Route\_Express\_West-LG



G-08-B016  
Route\_BlueNight-LG



G-08-B017  
Route\_BlueNight\_North-LG



G-08-B018  
Route\_BlueNight\_South-LG



G-08-B019  
Route\_BlueNight\_East-LG



G-08-B020  
Route\_BlueNight\_West-LG



G-08-B021  
Route\_Community-LG



G-08-B022  
Route\_Com\_North-LG



G-08-B023  
Route\_Com\_South-LG



G-08-B024  
Route\_Com\_East-LG



G-08-B025  
Route\_Com\_West-LG

## Bus bay ID – Suspended



G-08-B026  
Route\_Wheel-Trans-LG



G-08-B027  
Line 1\_North-LG



G-08-B028  
Line 1\_South-LG



G-08-B029  
Line 2\_East-LG



G-08-B030  
Line 2\_West-LG



G-08-B031  
Line 3\_East-LG



G-08-B032  
Line 3\_West-LG



G-08-B033  
Line 4\_East-LG



G-08-B034  
Line 4\_West-LG



G-08-B035  
Branch\_Regular-SM



G-08-B036  
Branch\_Regular\_Limit-  
ed-SM



G-08-B037  
Branch\_Express-SM



G-08-B038  
Branch\_BlueNight-SM



G-08-B039  
Branch\_Community-SM



Route\_Text-Centre\_Align



Sub\_Text-Centre\_Align



Sub\_Text-Top\_Align



VIVA-Kiwi-Temp-LG



VIVA-Kiwi-Temp-SM



YRT-Blue-Temp-LG



YRT-Blue-Temp-SM



YRT-Green-Temp-LG



YRT-Green-Temp-SM



YRT-Orange-Temp-LG



YRT-Orange-Temp-SM

### 3.7 Route numbering

#### Bus bay ID – Transom



G-08-B101  
Route\_Regular

G-08-B102  
Route\_Regular\_North

G-08-B103  
Route\_Regular\_South

G-08-B104  
Route\_Regular\_East

G-08-B105  
Route\_Regular\_West



G-08-B106  
Route\_Regular\_Limited

G-08-B107  
Route\_Reg\_Ltd\_North

G-08-B108  
Route\_Reg\_Ltd\_South

G-08-B109  
Route\_Reg\_Ltd\_East

G-08-B110  
Route\_Reg\_Ltd\_West



G-08-B111  
Route\_Express

G-08-B112  
Route\_Express\_North

G-08-B113  
Route\_Express\_South

G-08-B114  
Route\_Express\_East

G-08-B115  
Route\_Express\_West



G-08-B116  
Route\_BlueNight

G-08-B117  
Route\_BlueNight-2

G-08-B118  
Route\_BlueNight\_North

G-08-B119  
Route\_BlueNight\_East

G-08-B120  
Route\_BlueNight\_South



G-08-B121  
Route\_BlueNight\_West

G-08-B122  
Route\_Community

G-08-B123  
Route\_Com\_North

G-08-B124  
Route\_Com\_South

G-08-B125  
Route\_Com\_East

Bus bay ID – Transom



G-08-B126  
Route\_Cor\_West



G-08-B127  
Route\_Wheel-Trans



G-08-B128  
Line 1\_North



G-08-B129  
Line 1\_South



G-08-B130  
Line 2\_East



G-08-B131  
Line 2\_West



G-08-B132  
Line 3\_East



G-08-B133  
Line 3\_West




















G-08-B134  
Line 4\_East



G-08-B135  
Line 4\_West

3.7 Route numbering  
Signage

				
G-08-C001 Route_Regular	G-08-C002 Route_Regular_Limited	G-08-C003 Route_Express	G-08-C005 Route_BlueNight	G-08-C006 Route_Community
				
G-08-C101 Route_Regular_North	G-08-C102 Route_Regular_South	G-08-C103 Route_Regular_East	G-08-C104 Route_Regular_West	G-08-C105 Route_Limited_North
				
G-08-C106 Route_Limited_South	G-08-C107 Route_Limited_East	G-08-C108 Route_Limited_West		
				
G-08-C201 Shuttle_Line-1	G-08-C202 Shuttle_Line-2	G-08-C203 Shuttle_Line-3	G-08-C204 Shuttle_Line-4	



## Connecting routes



E-08-B001  
Route\_Regular-SM



E-08-B002  
Route\_Regular\_  
Limited-SM



E-08-B003  
Route\_Express-SM



E-08-B005  
Route\_BlueNight-SM



E-08-B006  
Route\_Community-SM



E-08-B007  
Route\_Wheel-Trans-SM



E-08-B008  
Route\_Regular\_N-SM



E-08-B009  
Route\_Regular\_S-SM



E-08-B010  
Route\_Regular\_E-SM



E-08-B011  
Route\_Regular\_W-SM



E-08-B012  
Route\_Express\_N-SM



E-08-B013  
Route\_Express\_S-SM



E-08-B014  
Route\_Express\_E-SM



E-08-B015  
Route\_Express\_W-SM



E-08-B016  
Route\_Reg\_Limit\_N-SM



E-08-B017  
Route\_Reg\_Limit\_S-SM



E-08-B018  
Route\_Reg\_Limit\_E-SM



E-08-B019  
Route\_Reg\_Limit\_W-SM



E-08-B024  
Route\_BlueNight\_  
Branch-SM



VIVA-Kiwi-Temp



YRT-Blue-Temp



YRT-Green-Temp



YRT-Orange-Temp


3.8 Logos  
TTC logos



G-03-A001  
TTC Logo BlackBG  
Double



G-03-A002  
TTC Logo White BG  
Double



G-03-B001  
IAMAW



G-03-B002  
ATU



G-03-B003  
Local 113



G-03-B004  
CUPE

## Transit partners



**Note:**

Refer to the *TTC Intermodal Wayfinding and Signage standards* for guidance on the correct use of Transit Partner logos

3.8 Logos  
Transit partners



G-03-C101  
TTC



G-03-C102  
YRT



G-03-C103  
VIVA



G-03-C104  
GO



G-03-C105  
UP



G-03-C106  
VIA



G-03-C107  
ZUM



G-03-C108  
Brampton



G-03-C109  
MiWay



G-03-C110  
DRT



G-03-C111  
Durham

Transit partners



G-03-C201  
TTC



G-03-C202  
YRT



G-03-C203  
GO



G-03-C204  
UP



G-03-C205  
VIA



G-03-C206  
ZUM



G-03-C207  
Brampton



G-03-C208  
MiWay



G-03-C209  
DRT



G-03-C210  
Durham

3.8 Logos  
Microtransit



G-03-H001  
Brickworks-Shuttle



G-03-H002  
IKEA-Shuttle



G-03-H003  
Lyft-Car



G-03-H004  
BikeShareToronto-Bike

## Points of interest



G-03-D001  
Art Gallery of Ontario



G-03-D002  
Art Gallery of Ontario



G-03-D003  
Air Canada



G-03-D004  
Air Canada



G-03-D005  
ROM



G-03-D006  
ROM



G-03-D007  
Hullmark Centre



G-03-D008  
Hullmark Centre



G-03-D009  
The Bay



G-03-D010  
The Bay



G-03-D011  
Science Centre



G-03-D012  
Science Centre



G-03-D013  
One Queen Street East



G-03-D014  
One Queen Street East



G-03-D015  
Yonge Dundas



G-03-D016  
Yonge Dundas




G-03-D017  
Elgin Winter Garden



G-03-D018  
Elgin Winter Garden



G-03-D019  
Elgin Winter Garden



G-03-D020  
Massey Hall



G-03-D021  
Municipal Parking



G-03-D022  
Yorkdale



G-03-D023  
PATH



G-03-D024  
Ontario



G-03-D025  
Toronto Eaton Centre

### 3.8 Logos

#### Points of interest



G-03-D026  
MaRS



G-03-D027  
MaRS



G-03-D028  
Fairmont Royal York



G-03-D029  
Emerald Park




G-03-D030  
Emerald Park



G-03-D031  
Information



G-03-D032  
Airport



G-03-D033  
Commerce Court



G-03-D034  
York University



G-03-D035  
Yonge Corporate Centre



G-03-D036  
Waterpark Place



G-03-D037  
Zoo



G-03-D038  
Zoo



G-03-D039  
Zoo



G-03-D040  
Zoo



G-03-D041  
Bloor Islington Place



G-03-D042  
Bloor Islington Place



G-03-D043  
Rogers Centre



G-03-D044  
Rogers Centre



G-03-D045  
CN Tower



G-03-D046  
Ripley's Aquarium



G-03-D047  
Metro Toronto  
Convention Centre



G-03-D048  
Metro Toronto  
Convention Centre



G-03-D049  
2 Queen East



G-03-D050  
York Mills Centre



## Points of interest



G-03-D051  
Pioneer Village




G-03-D052  
Yonge Sheppard Centre




G-03-D053  
Roy Thomson Hall



G-03-D054  
Yonge Eglinton Centre



G-03-D055  
Canada Square



G-03-D056  
OCAD



G-03-D057  
Marriott



G-03-D058  
Scotiabank Arena



G-03-D059  
Smart Centres



G-03-D060  
KPMG



G-03-D061  
Meridian Hall 1



G-03-D062  
Meridian Hall 2



G-03-D063  
Downsview Park



G-03-D064  
Brookfield Place



G-03-D065  
Royal Bank Plaza



G-03-D066  
Old Mill



G-03-D067  
Downsview Park  
Sports Centre



G-03-D068  
480 University



G-03-D069  
488 University



G-03-D070  
Meridian Arts Centre 1



G-03-D071  
Meridian Arts Centre 2



G-03-D072  
St Lawrence Centre



G-03-D073  
Exhibition Place



G-03-D074  
City Of Toronto



G-03-D075  
Toronto Public Library

Points of interest



G-03-D076  
Mel Lastman Square



G-03-D077  
North York Centre



G-03-D078  
NYC 5140 5160



G-03-D079  
Empress Walk



G-03-D080  
TDSB



G-03-D081  
U of T



G-03-D082  
Gardiner Museum



G-03-D083  
U of V



G-03-D084  
CIBC



G-03-D085  
EPlace



G-03-D086  
Union Food Court



G-03-D087  
10 Dundas East




G-03-D088  
Atrium on Bay

## Accessibility



G-04-A001  
Access



G-04-A002  
Elevator



G-04-A003  
Access-Ramp



G-04-A004  
Washroom-Access



G-04-A005  
Washroom-Access-Men



G-04-A006  
Washroom-Access-  
Women



G-04-A007  
Bridge-Access



G-04-A008  
Telephone



G-04-A009  
TelePhonicEar



G-04-A010  
Back In



G-04-A011  
Hearing Aid T



G-04-A012  
Accessible Path



G-04-A013  
Wheel-Trans



G-04-A014  
Accessible Assistance



G-04-A015  
Sign Language




G-04-A016  
Audio Description



G-04-A017  
BLE Beacon



G-04-A018  
Access Hub



G-04-A019  
Washroom Locker Men



G-04-A019  
Washroom Locker  
Women

### 3.9 Pictograms

#### Accessibility



G-04-A101  
Access



G-04-A102  
Elevator



G-04-A103  
Access\_Ramp



G-04-A104  
Washroom-Access



G-04-A105  
Washroom-Access-Men



G-04-A106  
Washroom-Access-Women



G-04-A107  
Access\_Walkway



G-04-A111  
Hearing\_Aid\_T



G-04-A113  
Wheel-Trans



G-04-A114  
Access\_Assistance



G-04-A115  
Sign Language



G-04-A116  
Audio\_Description



G-04-A121  
BLE\_Beacon



G-04-A122  
Access\_Station



G-04-A123  
Access\_House



G-04-A124  
Access\_Bus



G-04-A125  
Access\_Bus\_Enter



G-04-A126  
Access\_Bus\_Exit




G-04-A127  
Access\_Stop


## General



G-04-B001  
Escalator



G-04-B002  
Stairs



G-04-B003  
Subway



G-04-B004  
Streetcars



G-04-B005  
Buses



G-04-B006  
Shuttle Buses



G-04-B007  
Bus Platform



G-04-B008  
Bus Stop



G-04-B009  
Airport Buses



G-04-B010  
Bike Buses



G-04-B011  
Parking



G-04-B012  
Parking Lot 1



G-04-B013  
Parking Lot 2




G-04-B014  
Parking Lot 3



G-04-B015  
Parking Lot 4




G-04-B016  
Parking Lot 5



G-04-B017  
PPUDO



G-04-B017  
PPUDO\_Street Name



G-04-B018  
PPUDO\_North



G-04-B019  
PPUDO\_East



G-04-B020  
PPUDO\_South



G-04-B021  
PPUDO\_West



G-04-B022  
Taxi



G-04-B023  
Taxi Stand



G-04-B024  
Car

### 3.9 Pictograms

#### General



G-04-B025  
N-North



G-04-B026  
E-East



G-04-B027  
S-South



G-04-B028  
W-West



G-04-B029  
Washroom



G-04-B030  
Men



G-04-B031  
Women



G-04-B032  
Hospital



G-04-B033  
Street



G-04-B034  
Bicycles



G-04-B035  
Bike\_Lockers



G-04-B036  
Dismount



G-04-B037  
Bike Tools



G-04-B038  
Bike Pump



G-04-B039  
Bike\_Repairs



G-04-B040  
Bike\_Bus\_Rack



G-04-B041  
Telephones



G-04-B042  
Lost\_and\_Found



G-04-B043  
Luggage



G-04-B044  
Storage-Lockers



G-04-B045  
First\_Aid\_Kit



G-04-B046  
First\_Aid



G-04-B047  
Baby



G-04-B048  
Strollers



G-04-B049  
Security Camera

## General



G-04-B050  
Fountain



G-04-B051  
Trash



G-04-B52  
Garbage



G-04-B053  
Dogs\_On\_Leash



G-04-B054  
Stoop\_Scoop



G-04-B055  
Cameras



G-04-B056  
Coffee



G-04-B057  
Keys



G-04-B058  
Lock



G-04-B059  
Entry



G-04-B060  
Push Button Red



G-04-B061  
Shirt



G-04-B062  
Shoes



G-04-B063  
One Line



G-04-B064  
Two Lines



G-04-B065  
Waiting Area



G-04-B066  
Police



G-04-B067  
AED



G-04-B068  
AED



G-04-B069  
Wave\_To\_Open



G-04-B070  
Airport



G-04-B071  
Fares



G-04-B072  
POP



G-04-B073  
Collector



G-04-B074  
Information

## 3.9 Pictograms

### General



G-04-B075  
Information



G-04-B076  
Cell\_Phone



G-04-B079  
Map



G-04-B080  
WiFi



G-04-B081  
PRESTO




G-04-B082  
PRESTO Alt 1



G-04-B083  
PRESTO Alt 2



G-04-B084  
Fare\_Inspector



G-04-B085  
Compass



G-04-B086  
Train



G-04-B087  
Golf



G-04-B088  
Mail



G-04-B089  
CustomerServiceCentre



G-04-B090  
CSA



G-04-B091  
Ball\_Cap



G-04-B092  
Sunglasses



G-04-B093  
Contact




G-04-B094  
Security



G-04-B095  
Stations\_Group



G-04-B096  
TTC\_Pylon



G-04-B097  
Stop Marker



G-04-B098  
Baggage Wheeled



G-04-B099  
Multi People



G-04-B200  
TTC Pylon



G-04-B201  
Pay Fare Here



General



G-04-B202  
Public Library



G-04-B203  
PRESTO Card




G-04-B204  
PRESTO Card Tap

### 3.9 Pictograms


#### General



G-04-B101  
Escalator



G-04-B102  
Stairs



G-04-B103  
Subway



G-04-B104  
Streetcars



G-04-B105  
Buses



G-04-B106  
Shuttle Buses



G-04-B107  
Bus Platform



G-04-B108  
Bus Stop



G-04-B109  
Airport Buses



G-04-B110  
Bike Buses



G-04-B111  
Parking



G-04-B112  
Parking Lot 1



G-04-B113  
Parking Lot 2



G-04-B114  
Parking Lot 3



G-04-B115  
Parking Lot 4



G-04-B116  
Parking Lot 5



G-04-B117  
PPUDO



G-04-B117  
PPUDO Street Name



G-04-B118  
North



G-04-B119  
East



G-04-B120  
South



G-04-B121  
West



G-04-B122  
Taxi



G-04-B123  
TaxiStand



G-04-B124  
Car


## General



G-04-B125  
N-North



G-04-B126  
E-East



G-04-B127  
S-South



G-04-B128  
W-West



G-04-B129  
Washrooms



G-04-B130  
Men



G-04-B131  
Women



G-04-B132  
Hospital



G-04-B133  
Street




G-04-B134  
Bicycles




G-04-B135  
BikeLockers



G-04-B136  
Dismount



G-04-B137  
Bike Tools



G-04-B138  
Bike Pump



G-04-B139  
Bike Repairs



G-04-B140  
Bike Bus Rack



G-04-B141  
Telephones



G-04-B142  
Lost\_and\_Found



G-04-B143  
Luggage



G-04-B144  
Storage-Lockers



G-04-B145  
First\_Aid\_Kit



G-04-B146  
First\_Aid



G-04-B147  
Baby



G-04-B148  
Strollers



G-04-B149  
Security\_Camera

### 3.9 Pictograms

#### General



G-04-B150  
Fountain



G-04-B151  
Trash




G-04-B152  
Garbage



G-04-B153  
Dogs\_On\_Leash



G-04-B154  
Stoop\_Scoop



G-04-B155  
Cameras



G-04-B156  
Coffee




G-04-B157  
Keys



G-04-B158  
Lock



G-04-B159  
Entry



G-04-B160  
Push-Button-Red



G-04-B161  
Shirt



G-04-B162  
Shoes



G-04-B163  
One Line



G-04-B164  
Two Lines



G-04-B165  
Waiting Area




G-04-B166  
Police



G-04-B167  
AED



G-04-B168  
AED



G-04-B169  
Wave To Open



G-04-B170  
Airport



G-04-B171  
Fares



G-04-B172  
POP



G-04-B173  
Collector



G-04-B174  
Information

## General



G-04-B175  
Information



G-04-B176  
Cell Phone



G-04-B179  
Map



G-04-B180  
WiFi



G-04-B181  
PRESTO




G-04-B182  
PRESTO Alt 1




G-04-B183  
PRESTO Alt 2



G-04-B184  
Fare Inspector



G-04-B185  
Compass



G-04-B186  
Train



G-04-B187  
Golf



G-04-B188  
Mail




G-04-B189  
Customer Service Centre



G-04-B190  
CSA



G-04-B191  
Ball Cap



G-04-B192  
Sunglasses



G-04-B193  
Contact




G-04-B194  
Security




G-04-B195  
Stations Group



G-04-B196  
TTC Pylon Access



G-04-B197  
Stop Marker



G-04-B198  
Baggage Wheeled



G-04-B199  
Multi People



G-04-B300  
TTC Pylon



G-04-B301  
Pay Fare Here

## 3.9 Pictograms

### General



G-04-B302  
Public Library



G-04-B303  
PRESTO Card



G-04-B304  
PRESTO Card Tap

## Operational




G-04-C001  
BACS Rm



G-04-C002  
Bus Wash



G-04-C003  
Workstation



G-04-C004  
Compressor



G-04-C005  
Confined Space



G-04-C006  
Constricted Space




G-04-C007  
Electrical Rm



G-04-C008  
Expensed Parts



G-04-C009  
Fluids Pump Rm



G-04-C010  
HVAC



G-04-C011  
Library



G-04-C012  
Clipboard



G-04-C013  
Mechanical



G-04-C014  
Conference Rm



G-04-C015  
Multi People



G-04-C016  
Office




G-04-C017  
Plumbing Shop



G-04-C018  
Recycling



G-04-C019  
Repair Shop



G-04-C020  
Service Rm



G-04-C021  
Showers



G-04-C022  
Sign Up



G-04-C023  
Toolbox Storage




G-04-C024  
Training Rm



G-04-C025  
Transfers

### 3.9 Pictograms


#### Operational



G-04-C026  
UPS




G-04-C027  
Janitors



G-04-C028  
Battery Storage



G-04-C029  
Sprinklers




G-04-C030  
Lunch Rm




G-04-C031  
Transmission  
Changeover



G-04-C032  
Paint Shop



G-04-C033  
Pipe Chase



G-04-C034  
LAN Network




G-04-C035  
Used Parts Storage



G-04-C036  
Advertising Signs



G-04-C037  
Workshop



G-04-C038  
Hot Water Heater



G-04-C039  
Recreation




G-04-C040  
File Storage




G-04-C041  
Stock Rm



G-04-C042  
Plotter



G-04-C043  
Photocopier



G-04-C044  
Stationary



G-04-C045  
Welding



G-04-C041  
Stock Rm



G-04-C042  
Plotter



G-04-C048  
Storage Shelves



G-04-C049  
Carpenter Shop




G-04-C050  
Dust Collection




## Operational



G-04-C051  
Laundry Rm



G-04-C052  
Network Cords



G-04-C053  
Scrubber



G-04-C054  
Switch



G-04-C055  
Lockers



G-04-C056  
Lockers Men



G-04-C057  
Lockers Women



G-04-C058  
Dispatch




G-04-C059  
Quiet Rm



G-04-C060  
Loading Dock



G-04-C061  
Speaker



G-04-C062  
Seatbelt



G-04-C063  
Body Shop



G-04-C064  
Forklift



G-04-C065  
Recycling



G-04-C066  
Newspapers



G-04-C067  
Bottles



G-04-C068  
Coffee Cups



G-04-C069  
End Gate Right



G-04-C070  
End Gate Left



G-04-C071  
Radio Shop



G-04-C072  
Portable Radio



G-04-C073  
Cable Shop




G-04-C074  
Ladder



G-04-C075  
Ladder Fall


3.9 Pictograms  
Operational



G-04-C076  
Slide Gate




G-04-C077  
Garbage Can



G-04-C078  
Elev Machine Rm



G-04-C079  
Telephone Coms Rm



G-04-C080  
Esc Machine Rm



G-04-C081  
Bus De-Greasing




G-04-C082  
Garbage Bin



G-04-C083  
Recycling Bin



G-04-C084  
Exhaust Fan



G-04-C085  
Cable Pull Rm



G-04-C086  
Rolling Racks



G-04-C087  
Security Interview Rm

## Regulatory – Safety – Caution



G-04-D001  
No Smoking



G-04-D002  
No Entry



G-04-D003  
Entry



G-04-D004  
Entry with Restrictions



G-04-D005  
Bicycles Permitted



G-04-D006  
Service Animal



G-04-D007  
Service Animal



G-04-D008  
Pedestrian Overhead



G-04-D009  
Restricted Passage



G-04-D010  
Restricted Platform



G-04-D011  
Security Camera



G-04-D012  
Vehicle Overhead



G-04-D013  
Subway Permitted



G-04-D014  
Subway Restricted



G-04-D015  
Buses Permitted



G-04-D016  
Buses Restricted



G-04-D017  
Streetcars Permitted



G-04-D018  
Streetcars Restricted



G-04-D019  
Cars Permitted



G-04-D020  
Cars Restricted



G-04-D021  
Strong Wind



G-04-D022  
No Entry Workers



G-04-D023  
Entry Workers



G-04-D024  
Entry with  
Restrictions Workers



G-04-D025  
Water Faucet Permitted

### 3.9 Pictograms

#### Regulatory – Safety – Caution



G-04-D026  
Water Faucet Restricted



G-04-D027  
Do Not Drink  
From Faucet



G-04-D028  
Stop



G-04-D029  
Do Not Enter



G-04-D030  
TTC Employees Only



G-04-D031  
Non-Clearanc  
Through Station Left



G-04-D032  
Non-Clearance  
Through Station Right



G-04-D033  
Non-Clearance Left



G-04-D034  
Non-Clearance Right



G-04-D035  
Use Refuge  
Cages At Station



G-04-D036  
Use Refuge Cages



G-04-D037  
Non-Clearance  
Left Streetcars



G-04-D038  
Non-Clearance  
Right Streetcars



G-04-D039  
No Dumping



G-04-D040  
Caution  
Automatic Door



G-04-D041  
Push Door To Open



G-04-D042  
Non-Clearance  
Between Trains



G-04-D043  
Ladder Warning



G-04-D044  
Ladder Warning 2



G-04-D045  
Ladder Warning 3



G-04-D046  
Streetcar Pit



G-04-D047  
Subwaycar Pit



G-04-D048  
No Vaping




G-04-D049  
Max Throttle

## Regulatory – Safety – Caution



G-04-D101  
General Danger



G-04-D102  
High Voltage



G-04-D103  
Mind The Gap



G-04-D104  
Pedestrian Crossing



G-04-D105  
Slippery



G-04-D105  
Slippery



G-04-D107  
Stand Back Streetcars



G-04-D108  
Platform Fall Hazard



G-04-D109  
Watch Your Step



G-04-D110  
Explosive Hazard



G-04-D111  
Falling Debris



G-04-D112  
Open Pit



G-04-D113  
Strong Wind



G-04-D114  
Construction



G-04-D115  
Low Height



G-04-D123  
Walk Backwards



G-04-D124  
3 Point Contact Ladder



G-04-D125  
Oncoming Bus Traffic



G-04-D126  
Oncoming Train



G-04-D127  
Oncoming Streetcar



G-04-D128  
Oncoming Car



G-04-D129  
Restricted Platform Width



G-04-D130  
Tripping Hazard Curb



G-04-D131  
Confined Space



G-04-D132  
Forklift

### 3.9 Pictograms

#### Regulatory – Safety – Caution



G-04-D133  
Tripping Hazard Tracks



G-04-D134  
Kneeling Bus



G-04-D135  
Accessible Bus Ramp



G-04-D136  
Pedestrian Traffic



G-04-D137  
Car Pull



G-04-D138  
Step Up



G-04-D139  
Step Down



G-04-D140  
Steps Down



G-04-D141  
Vent Shaft



G-04-D142  
Chemical Irritants



G-04-D143  
Hot Surface



G-04-D144  
Hot Surface Hand



G-04-D145  
Ladder Fall



G-04-D146  
Pinch Crush



G-04-D147  
Truck



G-04-D148  
Steps Up




G-04-D149  
Moving Parts



G-04-D150  
Slip Ramp



G-04-D151  
Zombies



G-04-D152  
Heat Alert



G-04-D153  
Snow Alert



G-04-D154  
Rain Alert



G-04-D155  
Flood Alert



G-04-D156  
Fire Alert

## Regulatory – Safety – Caution



G-04-D201  
Fire




G-04-D202  
Fire Alarm



G-04-D203  
Fire Stairs Up



G-04-D204  
Fire Stairs Down



G-04-D205  
Fire Pull



G-04-D206  
Fire Extinguisher



G-04-D207  
Fire Hose



G-04-D208  
Siamese Hose



G-04-D209  
Fire Fighter



G-04-D210  
Fire Axe




G-04-D211  
FFA Vent Shaft




G-04-D212  
Fire Ladder



G-04-D213  
Cross Passage



G-04-D214  
Fire Electrical



G-04-D215  
Flood

### 3.9 Pictograms

#### Regulatory – Safety – Caution



G-04-D251  
Fire




G-04-D252  
Fire Alarm



G-04-D253  
Fire Stairs Up



G-04-D254  
Fire Stairs Down



G-04-D255  
Pull



G-04-D256  
Fire Extinguisher



G-04-D257  
Fire Hose



G-04-D258  
Siamese Hose



G-04-D259  
Fire Fighter



G-04-D260  
Fire Axe



G-04-D261  
FFA Vent Shaft



G-04-D262  
Fire Ladder



G-04-D263  
Cross Passage



G-04-D264  
Fire Electrical



G-04-D265  
Flood




G-04-D301  
Eye Wash



G-04-D302  
AED



G-04-D303  
First Aid



G-04-D304  
Shower



Regulatory – Safety – Caution



G-04-D401  
Class A  
Compressed Gas



G-04-D402  
Class B Combustible  
and Flammable



G-04-D403  
Class C Oxidizing



G-04-D404  
Class D Division 1  
Poisonous & Infectious



G-04-D405  
Class D Division 2  
Poisonous & Infectious



G-04-D406  
Class\_D-Division\_3-Poi-  
sonous\_&\_Infectious.eps



G-04-D407  
Class\_E-Corrosive.eps



G-04-D408  
Class\_F-Dangerous-  
ly\_Reactive.eps



G-04-D409  
Carcinogenic\_Materials.  
eps

### 3.9 Pictograms

#### Regulatory – Safety – Caution



G-04-D601  
Dust Respirator



G-04-D601  
Dust Respirator  
Reversed



G-04-D602  
Dust Respirator  
& Glasses



G-04-D603  
Dust Respirator  
& Googles



G-04-D605  
Full-Face Shield



G-04-D606  
Head & Hearing  
Protection



G-04-D607  
Head & Hearing  
Protection & Dust  
Respirator



G-04-D608  
Head & Hearing  
Protection & Dust  
Respirator & Glasses



G-04-D609  
Head & Hearing  
Protection & Dust  
Respirator & Googles



G-04-D610  
Head & Hearing  
Protection & Full-Face  
Respirator



G-04-D611  
Head & Hearing  
Protection &  
Full-Face Shield



G-04-D612  
Head & Hearing  
Protection Glasses



G-04-D613  
Head & Hearing  
Protection Googles



G-04-D614  
Head & Hearing  
Protection & Vapor  
Respirator



G-04-D615  
Head & Hearing  
Protection & Vapor  
Respirator & Glasses



G-04-D616  
Head & Hearing  
Protection & Vapor  
Respirator & Googles



G-04-D617  
Head Protection



G-04-D618  
Head Protection  
& Dust Respirator



G-04-D619  
Head Protection & Dust  
Respirator & Glasses



G-04-D620  
Head Protection  
& Dust Respirator  
& Googles



G-04-D621  
Head Protection  
& Full Face Respirator



G-04-D622  
Head Protection  
& Full-Face Shield



G-04-D623  
Head Protection  
& Glasses



G-04-D624  
Head Protection  
& Googles



G-04-D625  
Head Protection  
& Vapor Respirator

## Regulatory – Safety – Caution



G-04-D626  
Head Protection  
& Vapor Respirator  
& Glasses



G-04-D627  
Head Protection  
& Vapor Respirator  
& Goggles



G-04-D628  
Hearing Protection



G-04-D629  
Hearing Protection  
& Dust Respirator



G-04-D630  
Hearing Protection  
& Dust Respirator  
& Glasses



G-04-D631  
Hearing Protection  
& Dust Respirator  
& Goggles



G-04-D632  
Hearing Protection  
& Full-Face Respirator



G-04-D633  
Hearing Protection  
& Full-Face Shield



G-04-D634  
Hearing Protection  
& Glasses




G-04-D635  
Hearing Protection  
& Goggles



G-04-D636  
Hearing Protection  
& Vapor Respirator




G-04-D637  
Hearing Protection  
& Vapor Respirator  
& Glasses



G-04-D638  
Hearing Protection  
& Vapor Respirator  
& Goggles




G-04-D639  
Safety Boots



G-04-D640  
Safety Glasses



G-04-D641  
Safety Goggles



G-04-D642  
Safety Gloves




G-04-D643  
Vapor Respirator



G-04-D644  
Vapor Respirator  
& Glasses




G-04-D645  
Vapor Respirator  
& Goggles



G-04-D64  
TTC Vest




G-04-D647  
Full Body Suit



G-04-D648  
Body Suit




G-04-D649  
Respiratory Protection




G-04-D650  
Fall Arrest

3.9 Pictograms  
Regulatory – Safety – Caution



G-04-D651  
Arm Bands




G-04-D652  
Leg Bands




G-04-D653  
Safety Insulated Gloves



G-04-D654  
Bump Caps



G-04-D655  
Whistle



G-04-D656  
Flashlight



G-04-D657  
Portable Radio



G-04-D658  
Safety Insulated Shoes




G-04-D659  
Static Protection

## Prohibition



G-04-E001  
No Smoking



G-04-E002  
Do Not Enter



G-04-E003  
No Baby



G-04-E004  
No Bicycles



G-04-E005  
No Buses



G-04-E006  
No Cameras



G-04-E007  
No Car



G-04-E008  
No Dumping



G-04-E009  
No Entry



G-04-E010  
No Fares



G-04-E011  
No Food



G-04-E012  
No Littering



G-04-E013  
No Loitering



G-04-E014  
No Luggage



G-04-E015  
No Parking



G-04-E016  
No Pass Back



G-04-E017  
No Pets



G-04-E018  
No PPUDO



G-04-E019  
No Roller Blades



G-04-E020  
No Skateboarding



G-04-E021  
No Sledding



G-04-E022  
Do Not Feed Birds



G-04-E023  
No Streetcars




G-04-E024  
No Strollers



G-04-E025  
No Elevator

### 3.9 Pictograms Prohibition



G-04-E026  
No Fragrance



G-04-E027  
Turn Off Bus



G-04-E028  
Do Not Block



G-04-E029  
No Spitting



G-04-E030  
No Entry Workers



G-04-E031  
Do Not Drink  
From Faucet



G-04-E032  
Confined Space  
Do Not Enter




G-04-E033  
No Subway




G-04-E034  
No Cell Phones



G-04-E035  
No Trucks



G-04-E036  
No Fish



G-04-E037  
No Stairs



G-04-E038  
No Escalator



G-04-E039  
No Toilet



G-04-E040  
No Papertowel



G-04-E041  
No Recycling



G-04-E042  
No Access




G-04-E043  
Do Not Push  
Right Hand 1




G-04-E043  
Do Not Push  
Right Hand 2



G-04-E044  
Do Not Push  
Left Hand



G-04-E045  
No Stopping



G-04-E046  
No Power



G-04-E047  
Ball Cap



G-04-E048  
Sunglasses



G-04-E049  
No Vaping


## Prohibition



G-04-E050  
No Peanuts




G-04-E051  
No Geese



G-04-E052  
No Citrus



G-04-E053  
No Liquid



G-04-E054  
No Below 80 PSI



G-04-E055  
No Intercom



G-04-E056  
No PRESTO

### 3.9 Pictograms Prohibition



G-04-E101  
No Smoking



G-04-E102  
Do Not Enter



G-04-E103  
No Baby



G-04-E104  
No Bicycles



G-04-E105  
No Buses



G-04-E106  
No Cameras



G-04-E107  
No Car



G-04-E108  
No Dumping



G-04-E109  
No Entry



G-04-E110  
No Fares



G-04-E111  
No Food



G-04-E112  
No Littering



G-04-E113  
No Loitering



G-04-E114  
No Luggage



G-04-E115  
No Parking



G-04-E116  
No Pass Back



G-04-E117  
No Pets



G-04-E118  
No PPUDO



G-04-E119  
No Roller Blades



G-04-E120  
No Skateboarding



G-04-E121  
No Sledding



G-04-E122  
Do Not Feed Birds



G-04-E123  
No Streetcars




G-04-E124  
No Strollers



G-04-E125  
No Elevator



## Prohibition



G-04-E126  
No Fragrance



G-04-E127  
Turn Off Bus



G-04-E128  
Do Not Block



G-04-E129  
No Spitting



G-04-E130  
No Entry Workers



G-04-E131  
Do Not Drink From  
Faucet



G-04-E132  
Confined Space  
Do Not Enter



G-04-E133  
No Subway




G-04-E134  
No Cell Phones



G-04-E135  
No Trucks



G-04-E136  
No Fish



G-04-E137  
No Stairs



G-04-E138  
No Escalator



G-04-E139  
No Toilet



G-04-E140  
No Papertowel



G-04-E141  
No Recycling



G-04-E142  
No Access



G-04-E143  
No Stopping



G-04-E144  
No Crossing



G-04-E145  
No Vaping



G-04-E146  
No Peanuts



G-04-E147  
No Geese



G-04-E148  
No Citrus



G-04-E149  
No Liquid



G-04-E150  
Not Below 80 PSI

### 3.9 Pictograms

#### Prohibition



G-04-E151  
No Intercom



G-04-E152  
No PRESTO

## Prohibition



G-04-E209  
No Access



G-04-E235  
No Trucks



G-04-E236  
No Fish



G-04-E237  
No Stairs



G-04-E238  
No Escalator



G-04-E239  
No Toilet



G-04-E240  
No Papertowel



G-04-E241  
No Recycling



G-04-E242  
No Access

3.9 Pictograms  
Assistance Intercom



G-04-F001  
Assistance Intercom



G-04-F002  
AI-Emergency



G-04-F101  
Assistance Intercom



G-04-F102  
AI-Emergency

### 3.9 Pictograms

#### Priority seating



G-04-G001  
Disabled



G-04-G002  
Disabled



G-04-G003  
Service Animal



G-04-G004  
Service Animal



G-04-G005  
Elderly



G-04-G006  
Elderly



G-04-G007  
Expectant Mother



G-04-G008  
Expectant Mother



G-04-G009  
Mother Baby



G-04-G010  
Mother Baby



G-04-G101  
Disabled



G-04-G102  
Disabled



G-04-G103  
Service Animal



G-04-G104  
Service Animal



G-04-G105  
Elderly



G-04-G106  
Elderly



G-04-G107  
Expectant Mother



G-04-G108  
Expectant Mother



G-04-G109  
Mother Baby



G-04-G110  
Mother Baby

3.9 Pictograms  
Elevator buttons



G-06-A001  
Level 1 Black



G-06-A002  
Level 1 Red



G-06-A003  
Level 2 Black



G-06-A004  
Level 2 Red



G-06-A005  
Level 3 Black



G-06-A006  
Level 3 Red



G-06-A007  
Level 4 Black



G-06-A008  
Level 4 Red



G-06-A009  
Level 5 Black



G-06-A010  
Level 5 Red

## Text modules

Text modules have been developed in formats ideal for constructing TTC sign layouts. They encapsulate the correct weights, size and typeface set proportionally within the TTC's modular layout system. These text modules contribute to accuracy and consistency. Choice of which module is used is left to the designer based on a number of criteria:

Size of sign frame, orientation of information (flush-right or flush-left, size and amount of message content, etc). Consideration of viewing distance and information hierarchy may also influence module choice.



### 3.10 Text modules

#### Text modules



G-07-A021



G-07-A022




G-07-A023



G-07-A024



G-07-A025





## Text modules





4.0 Sign typology  
Table of contents



4.1	Insignia Pylon	4.2
4.2	Station entrances	4.16
4.3	Station information	4.32
4.4	Station fareline	4.52
4.5	Surface route platform	4.56
4.6	Directional	4.68
4.7	Elevator	4.84
4.8	Station platform	4.106
4.9	Station	4.110
4.10	Maps	4.132
4.11	Track level signage	4.134
4.12	Street level signage	4.148
4.13	Safety and security	4.150
4.14	Back of house	4.160
4.15	Front of house	4.168

## 4.1 Insignia Pylon

### Post mounted – Centred

<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Post mounted – Centred
<b>Description</b>	Freestanding, double sided, illuminated sign that identifies entry points into transit stations and other TTC properties
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>TTC logo</div> <div>● TTC Red</div> </div> <div> <div>Accessibility</div> <div>● Line 3 Blue</div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 3 mm translucent white, polished polycarbonate, custom shaped</li> <li>- First surface vinyl graphics, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Cabinet</b></p> <ul style="list-style-type: none"> <li>- 3 mm water cut and formed stainless steel signbody</li> </ul> <p><b>Posts and Hangers</b></p> <ul style="list-style-type: none"> <li>- Stainless steel components</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	TTC logo signbox: 1400 mm (w) x 545 mm (h) Accessibility signbox: 155 mm (w) x 155 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Custom, vacuum formed insignia face panels</li> <li>- Custom, vacuum formed accessible face panels</li> <li>- First surface vinyl graphics</li> </ul>
<b>Standard Drawing Detail</b>	SD101429.01 SD101429.05 SD101429.07 SD101429.08 SD101429.11 SD101429.14 SD101429.15 SD101429.17 SD101429.19 SD101429.20

Post mounted – Centred





## 4.1 Insignia Pylon

### Post mounted – Projected

<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Post mounted – Projected
<b>Description</b>	Freestanding, double sided, illuminated sign that identifies entry points into transit stations and other TTC properties
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>TTC logo</div> <div>● TTC Red</div> </div> <div> <div>Accessibility</div> <div>● Line 3 Blue</div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 3 mm translucent white, polished polycarbonate, custom shaped</li> <li>- First surface vinyl graphics, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Cabinet</b></p> <ul style="list-style-type: none"> <li>- 3 mm water cut and formed stainless steel signbody</li> </ul> <p><b>Posts and Hangers</b></p> <ul style="list-style-type: none"> <li>- Stainless steel components</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	<p>TTC logo signbox: 1400 mm (w) x 545 mm (h)</p> <p>Accessibility signbox: 155 mm (w) x 155 mm (h)</p>
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Custom, vacuum formed insignia face panels</li> <li>- Custom, vacuum formed accessible face panels</li> <li>- First surface vinyl graphics</li> </ul>
<b>Standard Drawing Detail</b>	<p>SD101429.02</p> <p>SD101429.04</p> <p>SD101429.06</p> <p>SD101429.09</p> <p>SD101429.10</p> <p>SD101429.12</p> <p>SD101429.13</p> <p>SD101429.16</p> <p>SD101429.17</p> <p>SD101429.19</p> <p>SD101429.20</p>

Post mounted – Projected





## 4.1 Insignia Pylon

### Surface mounted – Projected

<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Surface mounted – Projected
<b>Description</b>	Projected, double sided, illuminated sign that identifies entry points into transit stations and other TTC properties
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>TTC logo</div> <div>Accessibility</div> <div> <div></div> <div></div> </div> <div> <div>TTC Red</div> <div>Line 3 Blue</div> </div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 3 mm translucent white, polished polycarbonate, custom shaped</li> <li>- First surface vinyl graphics, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Cabinet</b></p> <ul style="list-style-type: none"> <li>- 3 mm water cut and formed stainless steel signbody</li> </ul> <p><b>Posts and Hangers</b></p> <ul style="list-style-type: none"> <li>- Stainless steel components</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	<p>TTC logo signbox: 1400 mm (w) x 545 mm (h)</p> <p>Accessibility signbox: 155 mm (w) x 155 mm (h)</p>
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Custom, vacuum formed insignia face panels</li> <li>- Custom, vacuum formed accessible face panels</li> <li>- First surface vinyl graphics</li> </ul>
<b>Standard Drawing Detail</b>	<p>SD101429.01</p> <p>SD101429.05</p> <p>SD101429.07</p> <p>SD101429.08</p> <p>SD101429.11</p> <p>SD101429.14</p> <p>SD101429.15</p> <p>SD101429.17</p> <p>SD101429.19</p> <p>SD101429.20</p>



Surface mounted – Projected





## 4.1 Insignia Pylon

### Surface mounted

<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Surface mounted
<b>Description</b>	Surface mounted, single sided, illuminated sign that identifies entry points into transit stations and other TTC properties
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>TTC logo</div> <div>Accessibility</div> <div> <div></div> <div></div> </div> <div> <div>TTC Red</div> <div>Line 3 Blue</div> </div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 3 mm translucent white, polished polycarbonate, custom shaped</li> <li>- First surface vinyl graphics, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Cabinet</b></p> <ul style="list-style-type: none"> <li>- 3 mm water cut and formed stainless steel signbody</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	TTC logo signbox: 1400 mm (w) x 545 mm (h) Accessibility signbox: 155 mm (w) x 155 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Custom, vacuum formed insignia face panel</li> <li>- Custom, vacuum formed accessible face panels</li> <li>- First surface vinyl graphics</li> </ul>
<b>Standard Drawing Detail</b>	TBD

Surface mounted




## 4.1 Insignia Pylon

### Post mounted – Centred Retrofit











<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Retrofit
<b>Description</b>	Freestanding, double sided, illuminated sign that identifies entry points into transit stations and other TTC properties
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>TTC logo</div> <div>Accessibility</div> <div> <div>TTC Red</div> <div>Line 3 Blue</div> </div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 3 mm translucent white, polished polycarbonate, custom shaped</li> <li>- First surface vinyl graphics, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Cabinet</b></p> <ul style="list-style-type: none"> <li>- 3 mm water cut and formed stainless steel signbody</li> </ul> <p><b>Posts and Hangers</b></p> <ul style="list-style-type: none"> <li>- Stainless steel components</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	<p>TTC logo signbox: 1400 mm (w) x 545 mm (h)</p> <p>Accessibility signbox: 155 mm (w) x 155 mm (h)</p>
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Custom, vacuum formed insignia face panels</li> <li>- Custom, vacuum formed accessible face panels</li> <li>- First surface vinyl graphics</li> </ul>
<b>Standard Drawing Detail</b>	<p>SD101429.18</p> <p>SD101429.20</p>

Post mounted – Centred Retrofit




## 4.1 Intermodal Pylon

### Post mounted – Intermodal – Centred

<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Intermodal – Centred
<b>Description</b>	Freestanding, double sided, illuminated sign that identifies entry points into transit stations with multiple agencies
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div> TTC logo GO Logo YRT Logo UP Logo VIA Logo ZUM Logo MiWay Logo Durham Logo Background Accessibility </div> <div>  TTC Red   GO   YRT   UP   VIA   Züm   MiWay   Durham   Black   Line 3 Blue </div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 4.5 mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Signbox</b></p> <ul style="list-style-type: none"> <li>- Signcomp Series 12 framing components, painted black</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	1000 mm (w)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 12 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	TBD

## Post mounted – Intermodal – Centred



**Insignia Pylon – Intermodal – Centred**  
Elevation  
1:100



**Intermodal logos signbox**  
Detail  
1:25


## 4.1 Intermodal Pylon

### Post mounted – Intermodal – Projected

<b>Sign family</b>	Insignia Pylon
<b>Sign type</b>	Intermodal – Projected
<b>Description</b>	Freestanding, double sided, illuminated sign that identifies entry points into transit stations with multiple agencies
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div> TTC logo GO Logo YRT Logo UP Logo VIA Logo ZUM Logo MiWay Logo Durham Logo Background Accessibility </div> <div> <span style="color: red;">●</span> TTC Red  <span style="color: green;">●</span> GO  <span style="color: blue;">●</span> YRT  <span style="color: black;">●</span> UP  <span style="color: yellow;">●</span> VIA  <span style="color: red;">●</span> Züm  <span style="color: orange;">●</span> MiWay  <span style="color: green;">●</span> Durham  <span style="color: black;">●</span> Black  <span style="color: blue;">●</span> Line 3 Blue </div> </div>
<b>Materials</b>	<p><b>Signface</b></p> <ul style="list-style-type: none"> <li>- 4.5 mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul> <p><b>Signbox</b></p> <ul style="list-style-type: none"> <li>- Signcomp Series 12 framing components, painted black</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	1000 mm (w)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 12 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	TBD



## Post mounted – Intermodal – Projected



**Insignia Pylon – Intermodal – Projected**  
Elevation  
1:100




**Intermodal logos signbox**  
Detail  
1:25

## 4.2 Station entrance


### Station identification (ID) – Stairwell

<b>Sign family</b>	Station entrance		
<b>Sign type</b>	Station identification (ID) – Stairwell		
<b>Description</b>	Framed, non-illuminated sign that identifies entry points into TTC stations and depicts the the modes of transit available and redirects customers to accessible entrances		
<b>Typeface</b>	Bloor-Yonge, uppercase		
<b>Colours</b>	TTC logo	●	TTC Red
	Background	●	Black
	Background	○	White
	Line 1	●	Line 1 Yellow
	Line 2	●	Line 2 Green
	Line 3	●	Line 3 Blue
	Line 4	●	Line 4 Purple
	Line 5	●	Line 5 Orange
	Line 6	●	Line 6 Grey
	Pictograms	○	White
	Text	○	White
	Accessibility	●	Line 3 Blue
<b>Materials</b>	<b>Signface</b> - 4.5 mm polycarbonate panels, non-glare, clear - Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films  <b>Signbox</b> - Signcomp Series 7 framing components, painted black		
<b>Power</b>	Regular power, LED components		
<b>Dimensions</b>	Signbox - Width to fit (w) x height to fit (h)		
<b>Fabrication</b>	- Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	SD101423.09		


Station identification (ID) – Stairwell



Station entrance – Station ID – Stairwell  
Elevation  
1:50




Signface  
Detail  
1:25



Signframe  
Detail  
1:25

**Design notes:**  
All staircase entrances require an accessible redirect to the closest accessible entrance at the station



## 4.2 Station entrance

### Station identification (ID) – Transom

<b>Sign family</b>	Station entrance		
<b>Sign type</b>	Station identification (ID) – Transom		
<b>Description</b>	Framed, illuminated signbox that identifies entry points into TTC stations and depicts the access features and modes of transit available		
<b>Typeface</b>	Bloor-Yonge, uppercase		
<b>Colours</b>	TTC logo	●	TTC Red
	Background	●	Black
	Line 1	●	Line 1 Yellow
	Line 2	●	Line 2 Green
	Line 3	●	Line 3 Blue
	Line 4	●	Line 4 Purple
	Line 5	●	Line 5 Orange
	Line 6	●	Line 6 Grey
	Pictograms	○	White
	Text	○	White
	Accessibility	●	Line 3 Blue
<b>Materials</b>	<b>Signface</b> - 4.5 mm polycarbonate panels, non-glare, clear - Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films  <b>Signbox</b> - Signcomp Series 7 framing components, painted black		
<b>Power</b>	Regular power, LED components		
<b>Dimensions</b>	Width to fit (w) x 400 mm (h)		
<b>Fabrication</b>	- Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	SD101423.21 SD101423.22 SD101423.23 SD101423.24 SD101423.25 SD101423.26 SD101423.27 SD101423.28		

## Station identification (ID) – Transom



Station entrance – Station identification (ID) – Transom

Elevation  
1:50



## 4.2 Station entrance


### Station identification (ID) – Double Transom

<b>Sign family</b>	Station entrance		
<b>Sign type</b>	Station identification (ID) – Double Transom		
<b>Description</b>	Framed, illuminated signbox that identifies entry points into TTC stations and depicts the access features and modes of transit available		
<b>Typeface</b>	Bloor-Yonge, uppercase		
<b>Colours</b>	TTC logo	●	TTC Red
	Background	●	Black
	Line 1	●	Line 1 Yellow
	Line 2	●	Line 2 Green
	Line 3	●	Line 3 Blue
	Line 4	●	Line 4 Purple
	Line 5	●	Line 5 Orange
	Line 6	●	Line 6 Grey
	Pictograms	○	White
	Text	○	White
	Accessibility	●	Line 3 Blue
<b>Materials</b>	<b>Signface</b> - 4.5 mm polycarbonate panels, non-glare, clear - Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films  <b>Signbox</b> - Signcomp Series 7 framing components, painted black		
<b>Power</b>	Regular power, LED components		
<b>Dimensions</b>	Width to fit (w) x 400 mm (h)		
<b>Fabrication</b>	- Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	SD101423.21 SD101423.22 SD101423.23 SD101423.24 SD101423.25 SD101423.26 SD101423.27 SD101423.28		

Station identification (ID) – Double Transom



Station entrance – Station identification (ID) – Double Transom  
Elevation  
1:100



Station entrance – Station identification (ID) – Double Transom  
Elevation  
1:100



Signframe  
Detail  
1:50



Signface  
Detail  
1:50


## 4.2 Station entrance

### Station identification (ID) – Transom – Intermodal


<b>Sign family</b>	Station entrance		
<b>Sign type</b>	Station identification (ID) – Transom – Intermodal		
<b>Description</b>	Framed, illuminated sign that identifies entry points into intermodal stations and depicts the access features and modes of transit available		
<b>Typeface</b>	Bloor-Yonge, uppercase		
<b>Colours</b>	TTC logo	●	TTC Red
	TTC Logo	●	TTC
	GO Logo	●	GO
	YRT Logo	●	YRT
	UP Logo	●	UP
	VIA Logo	●	VIA
	ZUM Logo	●	Züm
	MiWay Logo	●	MiWay
	Durham Logo	●	Durham
	Background	●	Black
	Background	○	White
	Line 1	●	Line 1 Yellow
	Line 2	●	Line 2 Green
	Line 3	●	Line 3 Blue
	Line 4	●	Line 4 Purple
	Line 5	●	Line 5 Orange
	Line 6	●	Line 6 Grey
	Pictograms	○	White
	Text	○	White
	Accessibility	●	Line 3 Blue
<b>Materials</b>	<b>Signface</b> - 4.5 mm polycarbonate panels, non-glare, clear - Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films  <b>Signbox</b> - Signcomp Series 7 framing components, painted black		
<b>Power</b>	Regular power, LED components		
<b>Dimensions</b>	Width to fit (w) x 400 mm (h)		
<b>Fabrication</b>	- Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	SD101423.21 SD101423.22 SD101423.23 SD101423.24 SD101423.25 SD101423.26 SD101423.27 SD101423.28		



Station identification (ID) – Transom – Intermodal



Station entrance – Station ID – Transom  
Elevation  
1:50




Signbox – Intermodal  
Detail  
1:50

## 4.2 Station entrance


### Doorbands – Exterior

<b>Sign family</b>	Station entrance
<b>Sign type</b>	Doorbands – Exterior
<b>Description</b>	Decals on entrance doors
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Text</div> <div>○ White</div> </div> <div> <div>Text</div> <div>● Black</div> </div> <div> <div>Background</div> <div>● Grey</div> </div> <div> <div>Background</div> <div>● TTC Red</div> </div> <div> <div>Pictograms</div> <div>● Line 3 Blue</div> </div> <div> <div>Pictograms</div> <div>○ White</div> </div> <div> <div>Pictograms</div> <div>● Black</div> </div> <div> <div>Pictograms</div> <div>● PRESTO Green</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-10, white</li> <li>- 3M Controltac 180MC-12, black, underlamine</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>
<b>Power</b>	N/A
<b>Dimensions</b>	Width to fit (w) x 200 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply white vinyl to black underlamine</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> </ul>

Doorbands – Exterior



Station entrance – Doorbands – Exterior  
Elevation  
1:50




Doorbands – Exterior  
Detail  
1:25

## 4.2 Station entrance


### Doorbands – Interior

<b>Sign family</b>	Station entrance
<b>Sign type</b>	Doorbands – Interior
<b>Description</b>	Decals on entrance doors
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Text</div> <div>○ White</div> </div> <div> <div>Text</div> <div>● Black</div> </div> <div> <div>Background</div> <div>● Grey</div> </div> <div> <div>Background</div> <div>● TTC Red</div> </div> <div> <div>Pictograms</div> <div>● Line 3 Blue</div> </div> <div> <div>Pictograms</div> <div>○ White</div> </div> <div> <div>Pictograms</div> <div>● Black</div> </div> <div> <div>Pictograms</div> <div>● PRESTO Green</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-10, white</li> <li>- 3M Controltac 180MC-12, black, underlamine</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>
<b>Power</b>	N/A
<b>Dimensions</b>	Width to fit (w) x 200 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply white vinyl to black underlamine</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> </ul>

Doorbands – Interior



Station entrance – Doorbands – Interior  
Elevation  
1:50



Doorbands – Interior  
Detail  
1:25

## 4.2 Station entrance


### Wheel-Trans No Show Board – Exterior

<b>Sign family</b>	Station entrance		
<b>Sign type</b>	Wheel-Trans No Show Board – Exterior		
<b>Description</b>	Decals adjacent to entrance doors		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Text	<input type="radio"/>	White
	Background	<input checked="" type="radio"/>	Black
	Pictograms	<input checked="" type="radio"/>	Line 3 Blue
	Pictograms	<input type="radio"/>	White
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-10, white</li> <li>- 3M Controltac 180MC-12, black, underlamine</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>		
<b>Power</b>	N/A		
<b>Dimensions</b>	600 mm (w) x 400 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply white vinyl to black underlamine</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Align with opposite side of decal</li> </ul>		

## Wheel-Trans No Show Board – Exterior



**Wheel-Trans Stop – No Show Board – Exterior**  
Elevation  
1:50



**Wheel-Trans No Show Board**  
Detail  
1:10

## 4.2 Station entrance

### Wheel-Trans No-Show Board – Interior


<b>Sign family</b>	Station entrance	
<b>Sign type</b>	Wheel-Trans No Show Board – Interior	
<b>Description</b>	Decals adjacent to entrance doors	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Text	○ White
	Background	● Black
	Background	● Line 3 Blue
	Pictograms	● Line 3 Blue
	Pictograms	○ White
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-10, white</li> <li>- 3M Controltac 180MC-12, black, underlamine</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>	
<b>Power</b>	N/A	
<b>Dimensions</b>	600 mm (w) x 400 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply white vinyl to black underlamine</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Align with opposite side of decal</li> </ul>	



Wheel-Trans No-Show Board – Interior



















Wheel-Trans Stop – No Show Board – Interior  
Elevation  
1:50




Wheel-Trans No Show Board  
Detail  
1:10

## 4.2 Station entrance


### Doorbands – Intermodal entrance

<b>Sign family</b>	Station entrance
<b>Sign type</b>	Doorbands – Intermodal entrance
<b>Description</b>	Decals on entrance doors
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div> TTC Logo GO Logo YRT Logo UP Logo VIA Logo ZUM Logo MiWay Logo Durham Logo Text Text Background Background Pictograms Pictograms Pictograms Pictograms </div> <div>  TTC Red   GO   YRT   UP   VIA   Züm   MiWay   Durham   White   Black   Grey   TTC Red   Line 3 Blue   White   Black   PRESTO Green </div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-10, white</li> <li>- 3M Controltac 180MC-12, black, underlamine</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>
<b>Power</b>	N/A
<b>Dimensions</b>	Width to fit (w) x 200 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply white vinyl to black underlamine</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> </ul>

Doorbands – Intermodal entrance



Station entrance – Doorbands – Exterior  
Elevation  
1:50




Doorbands – Intermodal  
Detail  
1:25

## 4.2 Station entrance

### Municipal address

<b>Sign family</b>	Station entrance		
<b>Sign type</b>	Municipal address		
<b>Description</b>	Placed on the exterior of TTC's properties with clear visibility to emergency services arriving on street		
<b>Typeface</b>	Swiss 721 BT Medium		
<b>Colours</b>	Numbers	●	Black
<b>Materials</b>			
<b>Power</b>	N/A		
<b>Dimensions</b>	Width to fit (w) x 200 mm (h)		
<b>Fabrication</b>	- Designer may use opaque vinyl or elect to fabricate with materials to compliment architectural finishes		
<b>Installation</b>	- Clean and prepare surface prior to installation		

## Municipal address



Station entrance – Municipal address  
Elevation  
1:50



200 min [ **991**  
Municipal address  
Detail  
1:25

## 4.3 Station information

### Decomissioned booth





<b>Sign family</b>	Station information
<b>Sign type</b>	Decomissioned booth
<b>Description</b>	Privacy band for decomissioned booths
<b>Typeface</b>	N/A
<b>Colours</b>	N/A
<b>Materials</b>	- 3M Scotchcal ElectroCut Graphic Film Series 7725-31, medium gray
<b>Power</b>	N/A
<b>Dimensions</b>	Width to fit (w) x 250 mm (h)
<b>Fabrication</b>	- 3M Scotchcal ElectroCut Graphic Film Series 7725-31, medium gray
<b>Installation</b>	- Clean and prepare surface prior to installation

Decomissioned booth




## 4.3 Station information

### Station hub

<b>Sign family</b>	Station information		
<b>Sign type</b>	Station hub		
<b>Description</b>	Station hubs include a non-illuminated information band and privacy band on the exterior of the hub. The interior includes a non-illuminated keystone mounted to the wall.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	TTC logo		TTC Red
	Text		White
	Background		Gray
	Background		White
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Scotchcal ElectroCut Graphic Film Series 7725-31 Medium Gray</li> <li>- 3M Scotchcal ElectroCut Graphic Film Series 7725-13 Tomato Red</li> <li>- 3M Scotchcal ElectroCut Graphic Film Series 7725-10 White</li> <li>- 6 mm white sintra</li> </ul>		
<b>Power</b>	N/A		
<b>Dimensions</b>	<ul style="list-style-type: none"> <li>- Information band: Width to fit (w) x 326 mm (h)</li> <li>- Privacy band: Width to fit (w) x 250 mm (h)</li> <li>- TTC logo: 895 mm (w) x 350 mm (h)</li> </ul>		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Information band: Cut white vinyl applied to 7725-13 tomato red band</li> <li>- Privacy band: Gray vinyl</li> <li>- TTC keystone: Digitally printed white sintra</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> </ul>		



Station hub




Station hub – Exterior  
Elevation  
1:50




Information band  
Detail  
1:25



Privacy band  
Detail  
1:25



Station hub – Interior  
Elevation  
1:50




TTC logo  
Detail  
1:25

## 4.3 Station information


### Plan your trip – Single panel – Surface mounted

<b>Sign family</b>	Station information		
<b>Sign type</b>	Plan your trip – Single panel – Surface mounted		
<b>Description</b>	Framed, illuminated sign that identifies key areas with trip planning materials including maps, station information and ride guides.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	- 0.5 mm white, translucent Styrene		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	- Type A graphic: 350 mm (w) x 1735 mm (h) - Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Aluminum extrusion framing components - Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	TBD		


Plan your trip – Single panel – Surface mounted



Plan your trip – Single panel – Surface mounted  
Elevation  
1:50



Type A graphic  
Detail  
1:25




Type B graphic  
Detail  
1:25

## 4.3 Station information


### Plan your trip – Double panel – Surface mounted

<b>Sign family</b>	Station information		
<b>Sign type</b>	Plan your trip – Double panel – Surface mounted		
<b>Description</b>	Framed, illuminated sign that identifies key areas with trip planning materials including maps, station information and ride guides.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	- 0.5 mm white, translucent Styrene		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	- Type A graphic: 350 mm (w) x 1735 mm (h) - Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Aluminum extrusion framing components - Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	TBD		


Plan your trip – Double panel – Surface mounted



Plan your trip – Double panel – Surface mounted  
Elevation  
1:50



Type A graphic  
Detail  
1:25




Type B graphic  
Detail  
1:25

## 4.3 Station information


### Plan your trip – Triple panel – Surface mounted

<b>Sign family</b>	Station information		
<b>Sign type</b>	Plan your trip – Triple - Wall mounted		
<b>Description</b>	Framed, illuminated sign that identifies key areas with trip planning materials including maps, station information and ride guides.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	- 0.5 mm white, translucent Styrene		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	- Type A graphic: 350 mm (w) x 1735 mm (h) - Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Aluminum extrusion framing components - Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	TBD		


Plan your trip – Triple panel – Surface mounted



Plan your trip – Triple panel – Surface mounted  
Elevation  
1:50



Type A graphic  
Detail  
1:25



Type B graphic  
Detail  
1:25


## 4.3 Station information

### Plan your trip – Single – Freestanding


<b>Sign family</b>	Station information		
<b>Sign type</b>	Plan your trip – Triple - Wall mounted		
<b>Description</b>	Framed, illuminated sign that identifies key areas with trip planning materials including maps, station information and ride guides.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	- 0.5 mm white, translucent Styrene		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	- Type A graphic: 350 mm (w) x 1735 mm (h) - Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Aluminum extrusion framing components - Signcomp Series 7 post and framing components, painted black - Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	TBD		




Plan your trip – Single – Freestanding



Plan your trip – Single – Freestanding  
Elevation  
1:50



Type A graphic  
Detail  
1:25




Type B graphic  
Detail  
1:25

## 4.3 Station information


### Plan your trip – Double – Freestanding

<b>Sign family</b>	Station information		
<b>Sign type</b>	Plan your trip – Triple – Wall mounted		
<b>Description</b>	Framed, illuminated sign that identifies key areas with trip planning materials including maps, station information and ride guides.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	- 0.5 mm white, translucent Styrene		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	- Type A graphic: 350 mm (w) x 1735 mm (h) - Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Aluminum extrusion framing components - Signcomp Series 7 post and framing components, painted black - Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	TBD		


Plan your trip – Double – Freestanding



Plan your trip – Double – Freestanding  
Elevation  
1:50



Type A graphic  
Detail  
1:25





Type B graphic  
Detail  
1:25

## 4.3 Station information


### Plan your trip – Triple – Freestanding

<b>Sign family</b>	Station information		
<b>Sign type</b>	Plan your trip – Triple – Freestanding		
<b>Description</b>	Framed, illuminated sign that identifies key areas with trip planning materials including maps, station information and ride guides.		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	- 0.5 mm white, translucent Styrene		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	- Type A graphic: 350 mm (w) x 1735 mm (h) - Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Aluminum extrusion framing components - Signcomp Series 7 post and framing components, painted black - Mechanical fastening to suit available structural/surface conditions		
<b>Standard Drawing Detail</b>	TBD		

Plan your trip – Triple – Freestanding



**Type A graphic**  
Detail  
1:25





**Type B graphic**  
Detail  
1:25

## 4.3 Station information

### Fares

<b>Sign family</b>	Station information		
<b>Sign type</b>	Fares		
<b>Description</b>	Framed, illuminated sign that identifies areas to purchase fare media for station access		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5 mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>		
<b>Power</b>	- Regular power, LED components		
<b>Dimensions</b>	<p><b>Surface mounted</b></p> <ul style="list-style-type: none"> <li>- 430 mm (w) x 2430 mm (h)</li> </ul> <p><b>Projected</b></p> <ul style="list-style-type: none"> <li>- 240 mm (w) x 240 mm (h)</li> </ul>		
<b>Fabrication</b>	<p><b>Surface mounted</b></p> <ul style="list-style-type: none"> <li>- Signcomp Series 7 post and framing components, painted red</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul> <p><b>Projected</b></p> <ul style="list-style-type: none"> <li>- Signcomp Series 3 post and framing components, painted red</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>		
<b>Standard Drawing Detail</b>	TBD		

Fares






## 4.3 Station information

### Assistance Intercom

<b>Sign family</b>	Station information																						
<b>Sign type</b>	Assistance Intercom																						
<b>Description</b>	Freestanding or wall mounted, single sided, non-illuminated sign panel that includes an information or emergency button for customers. These are typically placed near farelines or DWAs.																						
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Light, upper & lowercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot																						
<b>Colours</b>	<table> <tr> <td>Tactile text</td><td>○ White</td></tr> <tr> <td>Braille</td><td>● Rich black</td></tr> <tr> <td>Background</td><td>● Rich black</td></tr> <tr> <td>Text</td><td>○ White</td></tr> <tr> <td>Pictograms</td><td>○ White</td></tr> <tr> <td>Pictograms</td><td>● Line 3 Blue</td></tr> <tr> <td>Pictograms</td><td>● TTC Red</td></tr> <tr> <td>Background</td><td>● Rich black</td></tr> <tr> <td>Blue border</td><td>● Line 3 Blue</td></tr> <tr> <td>Red border</td><td>● TTC Red</td></tr> <tr> <td>Cabinet</td><td>● Safety yellow</td></tr> </table>	Tactile text	○ White	Braille	● Rich black	Background	● Rich black	Text	○ White	Pictograms	○ White	Pictograms	● Line 3 Blue	Pictograms	● TTC Red	Background	● Rich black	Blue border	● Line 3 Blue	Red border	● TTC Red	Cabinet	● Safety yellow
Tactile text	○ White																						
Braille	● Rich black																						
Background	● Rich black																						
Text	○ White																						
Pictograms	○ White																						
Pictograms	● Line 3 Blue																						
Pictograms	● TTC Red																						
Background	● Rich black																						
Blue border	● Line 3 Blue																						
Red border	● TTC Red																						
Cabinet	● Safety yellow																						
<b>Materials</b>	- 1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite																						
<b>Power</b>	- Power and communications cables per communications standards																						
<b>Dimensions</b>	200 mm (w) x 500 mm (h)																						
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, digitally printed graphics and text, using a multi-layered, CMYK additive printing process</li> <li>- Raised tactile and Braille components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> </ul>																						
<b>Installation</b>	<p><b>Braille and tactile face panels:</b></p> <ul style="list-style-type: none"> <li>- Mechanically fastened to pre-cut and drilled matching metal backer panel, w/ welded studs, electronics and components</li> <li>- Screws: 3mm Ø, Stainless Steel, Tamper-Resistant, Spanner Flat Head Machine Screws, w/ 4 Points of Attachment. Colour: Black Paint Finish, to match Face Panel</li> <li>- To be integrated into Interior Elevator Control Panel</li> </ul> <p><b>Intercom cabinet:</b></p> <ul style="list-style-type: none"> <li>- Signcomp Series 7 components</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>																						
<b>Standard Drawing Detail</b>	- Units to be supplied through Communications group																						



Assistance Intercom




## 4.4 Station fareline


### Fare gate decals

<b>Sign family</b>	Station fareline		
<b>Sign type</b>	Fare gate decals		
<b>Description</b>	May be used to identify specific directional information, such as accessible pathways or where to tap PRESTO cards		
<b>Typeface</b>	N/A		
<b>Colours</b>	Background	●	Line 3 Blue
	Accessibility	○	White
	Border	○	White
	Black	●	Black
	Overlamine	○	Matte clear
	Text / logo	○	White
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-10, white</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> <li>- First surface, digital print graphics and/or text</li> </ul>		
<b>Power</b>	N/A		
<b>Dimensions</b>	Access decal – Large: 150 mm (w) x 150 mm (h) Access decal – Small: 75 mm (w) x 75 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply white vinyl to black underlamine</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>		


Fare gate decals



Fare gate decals  
Elevation  
1:50



Access decal – Large  
Detail  
1:5




Access decal – Small  
Detail  
1:5

## 4.4 Station fareline

### Fare gate sensor decals

<b>Sign family</b>	Station fareline		
<b>Sign type</b>	Fare gate sensor decals		
<b>Description</b>	Decal placed on PRESTO readers		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase		
<b>Colours</b>	Border	<input type="radio"/>	Clear
	Overlamine	<input type="radio"/>	Matte clear
	Text	<input type="radio"/>	White
<b>Materials</b>	- 3M Scotchcal 8520, clear, matte - First surface, digital print graphics and/or text		
<b>Power</b>	N/A		
<b>Dimensions</b>	35 mm (w) x 10 mm (h)		
<b>Fabrication</b>	- 3M Scotchcal 8520, clear, matte - First surface, direct print graphics and/or text		

Fare gate sensor decals



Fare gate sensor decals  
Plan  
1:2




Tap Here decal  
Detail  
1:1

## 4.5 Surface route platform


### Connecting routes – Single panel – Surface mounted

<b>Sign family</b>	Surface route platform		
<b>Sign type</b>	Connecting routes – Single panel – Surface mounted		
<b>Description</b>	Wall mounted, illuminated sign panels that include information about routes departing from the station. These signs are located at surface route platforms.		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	Illuminated: 6 mm white translucent styrene (with anti-static protection applied to both sides) Non-illuminated: 4 mm coroplast (with anti-static protection applied to both sides)		
<b>Power</b>	Regular power, LED components		
<b>Dimensions</b>	Type A graphic: 350 mm (w) x 1735 mm (h) Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Aluminum extrusion framing components</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>		
<b>Standard Drawing Detail</b>	TBD		


Connecting routes – Single panel – Surface mounted



Connecting routes – Wall mounted  
Elevation  
1:50



Type A graphic  
Detail  
1:25



Type B graphic  
Detail  
1:25


## 4.5 Surface route platform

### Connecting routes – Single panel – Freestanding


<b>Sign family</b>	Surface route platform		
<b>Sign type</b>	Connecting routes – Single panel – Freestanding		
<b>Description</b>	Freestanding, illuminated sign panels that include information about routes departing from the station. These signs are located at surface route platforms.		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	TTC Red
	Pictograms	○	White
	Text	○	White
<b>Materials</b>	Illuminated: Digital print to 6 mm white translucent styrene (with anti-static protection applied to both sides) Non-illuminated: Digital print to 4 mm coroplast (with anti-static protection applied to both sides)		
<b>Power</b>	Regular power, LED components		
<b>Dimensions</b>	Type A graphic: 350 mm (w) x 1735 mm (h) Type B graphic: 1195 mm (w) x 1725 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Aluminum extrusion framing components</li> <li>- Signcomp Series 7 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>		
<b>Standard Drawing Detail</b>	TBD		




## Connecting routes – Single panel – Freestanding



**Connecting routes – Freestanding**  
Elevation  
1:50



**Type A graphic**  
Detail  
1:25




**Type B graphic**  
Detail  
1:25

## 4.5 Surface route platform

### Route ID – Transom


<b>Sign family</b>	Surface route platform
<b>Sign type</b>	Route ID – Transom
<b>Description</b>	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>Line 1</div> <div>Line 2</div> <div>Line 3</div> <div>Line 4</div> <div>Line 5</div> <div>Line 6</div> <div>Pictograms</div> <div>Text</div> <div>Accessibility</div> <div>Regular route</div> <div>Express route</div> <div>Blue Night Network</div> <div>Community Bus</div> <div>Shuttle bus</div> </div> <div> <div>● Black</div> <div>● Line 1 Yellow</div> <div>● Line 2 Green</div> <div>● Line 3 Blue</div> <div>● Line 4 Purple</div> <div>● Line 5 Orange</div> <div>● Line 6 Grey</div> <div>○ White</div> <div>○ White</div> <div>● Line 3 Blue</div> <div>● TTC Red</div> <div>● Line 2 Green</div> <div>● Safety Partner Blue</div> <div>● Dark Grey</div> <div>● Line 5 Orange</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5 mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	Width to fit (w) x 400 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	SD101423.21 SD101423.22 SD101423.23 SD101423.24 SD101423.25 SD101423.26 SD101423.27 SD101423.28

Route ID – Transom



Surface route platform – Transom  
Elevation  
1:50


**Design notes:**  
For routes to the left or right of the doors, divide the signface in two and center the route on the signface (Option 1).  
  
For routes directly outside the doors, center the content in the middle of the signbox. The middle will be 2400 mm with the remaining width split into another signfaces (Option 2).



Transom – Option 1  
Detail  
1:50



Transom – Option 2  
Detail  
1:50



Signface  
Detail  
1:50

Route modules      H Channel

## 4.5 Surface route platform


### Route ID – Suspended

<b>Sign family</b>	Surface route platform
<b>Sign type</b>	Route ID – Suspended
<b>Description</b>	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>Line 1</div> <div>Line 2</div> <div>Line 3</div> <div>Line 4</div> <div>Line 5</div> <div>Line 6</div> <div>Pictograms</div> <div>Text</div> <div>Accessibility</div> <div>Regular route</div> <div>Express route</div> <div>Blue Night Network</div> <div>Community Bus</div> <div>Shuttle bus</div> </div> <div> <div>● Black</div> <div>● Line 1 Yellow</div> <div>● Line 2 Green</div> <div>● Line 3 Blue</div> <div>● Line 4 Purple</div> <div>● Line 5 Orange</div> <div>● Line 6 Grey</div> <div>○ White</div> <div>○ White</div> <div>● Line 3 Blue</div> <div>● TTC Red</div> <div>● Line 2 Green</div> <div>● Safety Partner Blue</div> <div>● Dark Grey</div> <div>● Line 5 Orange</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5 mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	1200 mm (w) x 400 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	TBD


Route ID – Suspended



Surface route platform – Route ID – Suspended  
Elevation  
1:100



Route ID – Suspended  
Detail  
1:20




Route ID – Suspended  
Detail  
1:20

## 4.5 Surface route platform


### Route ID – Stop marker

<b>Sign family</b>	Surface route platform
<b>Sign type</b>	Route ID – Stop marker
<b>Description</b>	
<b>Typeface</b>	Swiss 721 BT Bold Condensed, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>● Black</div> </div> <div> <div>Line 1</div> <div>● Line 1 Yellow</div> </div> <div> <div>Line 2</div> <div>● Line 2 Green</div> </div> <div> <div>Line 3</div> <div>● Line 3 Blue</div> </div> <div> <div>Line 4</div> <div>● Line 4 Purple</div> </div> <div> <div>Line 5</div> <div>● Line 5 Orange</div> </div> <div> <div>Line 6</div> <div>● Line 6 Grey</div> </div> <div> <div>Pictograms</div> <div>○ White</div> </div> <div> <div>Text</div> <div>○ White</div> </div> <div> <div>Accessibility</div> <div>● Line 3 Blue</div> </div> <div> <div>Regular route</div> <div>● TTC Red</div> </div> <div> <div>Express route</div> <div>● Line 2 Green</div> </div> <div> <div>Blue Night Network</div> <div>● Safety Partner Blue</div> </div> <div> <div>Community Bus</div> <div>● Dark Grey</div> </div> <div> <div>Shuttle bus</div> <div>● Line 5 Orange</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Scotchlite Series 680-72, 76, 71 Reflective Film</li> <li>- 3M Scotchlite Series 680-10 Reflective Film</li> <li>- Gerber vinyl graphics</li> </ul>
<b>Power</b>	N/A
<b>Dimensions</b>	<ul style="list-style-type: none"> <li>- Double sided round head: 160 mm (w) x 920 mm (h)</li> <li>- Single sided kydex pan: 220 mm (w) x 915 mm (h)</li> </ul>
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Vinyl applied first surface to round head / kydex pan</li> <li>- Note: 2 kydex pan panels per each stop</li> </ul>
<b>Standard Drawing Detail</b>	TBD

Route ID – Stop marker



Surface route platform - Stop marker  
Elevation  
1:100



Stop marker  
Detail  
1:10


## 4.5 Surface route platform

### Access Hub

<b>Sign family</b>	Surface route platform																				
<b>Sign type</b>	Access Hub																				
<b>Description</b>																					
<b>Typeface</b>	Bloor-Yonge, uppercase Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Light, upper & lowercase Grade 1 Braille – 6 mm cell, w/ 1.5 mm diameter dot																				
<b>Colours</b>	<table> <tr> <td>Background</td><td>● Rich black</td></tr> <tr> <td>Background</td><td>● Line 3</td></tr> <tr> <td>Pictograms</td><td>○ White</td></tr> <tr> <td>Pictograms</td><td>● Line 3</td></tr> <tr> <td>Pictograms</td><td>● TTC Red</td></tr> <tr> <td>Pictograms</td><td>● Rich black</td></tr> <tr> <td>Text</td><td>○ White</td></tr> <tr> <td>Tactile text</td><td>○ White</td></tr> <tr> <td>TTC logo</td><td>● TTC Red</td></tr> <tr> <td>Braille</td><td>● Rich black</td></tr> </table>	Background	● Rich black	Background	● Line 3	Pictograms	○ White	Pictograms	● Line 3	Pictograms	● TTC Red	Pictograms	● Rich black	Text	○ White	Tactile text	○ White	TTC logo	● TTC Red	Braille	● Rich black
Background	● Rich black																				
Background	● Line 3																				
Pictograms	○ White																				
Pictograms	● Line 3																				
Pictograms	● TTC Red																				
Pictograms	● Rich black																				
Text	○ White																				
Tactile text	○ White																				
TTC logo	● TTC Red																				
Braille	● Rich black																				
<b>Materials</b>	<p><b>Acrylic:</b></p> <ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- Raised tactile components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> </ul> <p><b>Loop ID:</b></p> <ul style="list-style-type: none"> <li>- 3 mm Dibond panels, white, by Alusuisse Composites Inc.</li> <li>- First surface, direct print graphics and/or text, using CMYK colours</li> </ul> <p><b>Vinyl:</b></p> <ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-010, white</li> <li>- 3M Controltac 180MC-12, black, underlamine</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> <li>- First surface, direct print graphics and/or text</li> </ul>																				
<b>Power</b>	N/A																				
<b>Dimensions</b>	Access Hub: 600 mm (w) x 865 mm (h) WT decal: 625 mm (w) x 400 mm (h) Wave below: 110 mm (w) x 200 mm (h) Loop ID: 1200 mm (w) x 1200 mm (h)																				
<b>Fabrication</b>																					
<b>Standard Drawing Detail</b>	S1043418 SK3102																				




Access Hub




Access Hub – Shelter – Exterior  
Elevation  
1:100

Loop ID  
Elevation  
1:100



Access Hub – Shelter – Interior  
Elevation  
1:100

Access Hub – Wave Here  
Detail  
1:50



Access Hub  
Detail  
1:20

WT decal – Exterior  
Detail  
1:20

WT decal – Interior  
Detail  
1:20


Wave Below  
Detail  
1:20

## 4.6 Directional

### Suspended signage

<b>Sign family</b>	Directional
<b>Sign type</b>	Suspended signage
<b>Description</b>	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div> <div>●</div> Black </div> </div> <div> <div>Line 1</div> <div> <div>●</div> Line 1 Yellow </div> </div> <div> <div>Line 2</div> <div> <div>●</div> Line 2 Green </div> </div> <div> <div>Line 3</div> <div> <div>●</div> Line 3 Blue </div> </div> <div> <div>Line 4</div> <div> <div>●</div> Line 4 Purple </div> </div> <div> <div>Line 5</div> <div> <div>●</div> Line 5 Orange </div> </div> <div> <div>Line 6</div> <div> <div>●</div> Line 6 Grey </div> </div> <div> <div>Pictograms</div> <div> <div>○</div> White </div> </div> <div> <div>Text</div> <div> <div>○</div> White </div> </div> <div> <div>Accessibility</div> <div> <div>●</div> Line 3 Blue </div> </div> <div> <div>Regular route</div> <div> <div>●</div> TTC Red </div> </div> <div> <div>Express route</div> <div> <div>●</div> Line 2 Green </div> </div> <div> <div>Blue Night Network</div> <div> <div>●</div> Safety Partner Blue </div> </div> <div> <div>Community Bus</div> <div> <div>●</div> Dark Grey </div> </div> <div> <div>Shuttle bus</div> <div> <div>●</div> Line 5 Orange </div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	Varies (w) x 300–400 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	SD101423.01 SD101423.02 SD101423.03 SD101423.04 SD101423.05 SD101423.06 SD101423.07 SD101423.08

Suspended signage



**Directional – Suspended signage**  
Elevation  
1:50

**Design notes:**  
For signage suspended over a common staircase and escalator, place the arrow closest to the staircase.


For signage suspended over a staircase, the arrow should be placed on the right side of the sign.

All graphics paired with forward or down arrows should be centered on the signface.

For signs like the above, the arrows should be mirrored.



**Suspended signbox**  
Detail  
1:20




**Signface**  
Detail  
1:20

## 4.6 Directional

### Post mounted signage

<b>Sign family</b>	Directional
<b>Sign type</b>	Post mounted signage
<b>Description</b>	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>Line 1</div> <div>Line 2</div> <div>Line 3</div> <div>Line 4</div> <div>Line 5</div> <div>Line 6</div> <div>Pictograms</div> <div>Text</div> <div>Accessibility</div> <div>Regular route</div> <div>Express route</div> <div>Blue Night Network</div> <div>Community Bus</div> <div>Shuttle bus</div> </div> <div> <div>● Black</div> <div>● Line 1 Yellow</div> <div>● Line 2 Green</div> <div>● Line 3 Blue</div> <div>● Line 4 Purple</div> <div>● Line 5 Orange</div> <div>● Line 6 Grey</div> <div>○ White</div> <div>○ White</div> <div>● Line 3 Blue</div> <div>● TTC Red</div> <div>● Line 2 Green</div> <div>● Safety Partner Blue</div> <div>● Dark Grey</div> <div>● Line 5 Orange</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	250–400 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	TBD

Post mounted signage




**Directional – Post mounted signage**  
Elevation  
1:50

**Design notes:**  
For signage suspended over a common staircase and escalator, place the arrow closest to the staircase.


For signage suspended over a staircase, the arrow should be placed on the right side of the sign.

All graphics paired with forward or down arrows should be centered on the signface.

For signs like the above, the arrows should be mirrored.



**Suspended signbox**  
Detail  
1:20




**Signface**  
Detail  
1:20

## 4.6 Directional

### Surface mounted signage – Single message

<b>Sign family</b>	Directional																				
<b>Sign type</b>	Surface mounted signage – Single message																				
<b>Description</b>	Surface mounted directional signs are single sided, illuminated signs																				
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase																				
<b>Colours</b>	<table> <tr> <td>Background</td><td>● Black</td></tr> <tr> <td>Line 1</td><td>● Line 1 Yellow</td></tr> <tr> <td>Line 2</td><td>● Line 2 Green</td></tr> <tr> <td>Line 3</td><td>● Line 3 Blue</td></tr> <tr> <td>Line 4</td><td>● Line 4 Purple</td></tr> <tr> <td>Line 5</td><td>● Line 5 Orange</td></tr> <tr> <td>Line 6</td><td>● Line 6 Grey</td></tr> <tr> <td>Pictograms</td><td>○ White</td></tr> <tr> <td>Text</td><td>○ White</td></tr> <tr> <td>Accessibility</td><td>● Line 3 Blue</td></tr> </table>	Background	● Black	Line 1	● Line 1 Yellow	Line 2	● Line 2 Green	Line 3	● Line 3 Blue	Line 4	● Line 4 Purple	Line 5	● Line 5 Orange	Line 6	● Line 6 Grey	Pictograms	○ White	Text	○ White	Accessibility	● Line 3 Blue
Background	● Black																				
Line 1	● Line 1 Yellow																				
Line 2	● Line 2 Green																				
Line 3	● Line 3 Blue																				
Line 4	● Line 4 Purple																				
Line 5	● Line 5 Orange																				
Line 6	● Line 6 Grey																				
Pictograms	○ White																				
Text	○ White																				
Accessibility	● Line 3 Blue																				
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>																				
<b>Power</b>	Regular power, LED components																				
<b>Dimensions</b>	Varies (w) x 300 mm (h)																				
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>																				
<b>Standard Drawing Detail</b>	TBD																				

Surface mounted signage – Single message




**Directional – Surface mounted – Single message**  
Elevation  
1:50

**Design notes:**  
45-degree arrows are only used on signs at the top or bottom of stairs and escalators.



**Surface mounted signbox**  
Detail  
1:25



**Signface**  
Detail  
1:25


## 4.6 Directional

### Surface mounted signage – Multi message


<b>Sign family</b>	Directional
<b>Sign type</b>	Surface mounted signage – Multi message
<b>Description</b>	Surface mounted directional signs are single sided, illuminated signs
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>Line 1</div> <div>Line 2</div> <div>Line 3</div> <div>Line 4</div> <div>Line 5</div> <div>Line 6</div> <div>Pictograms</div> <div>Text</div> <div>Accessibility</div> </div> <div> <div>● Black</div> <div>● Line 1 Yellow</div> <div>● Line 2 Green</div> <div>● Line 3 Blue</div> <div>● Line 4 Purple</div> <div>● Line 5 Orange</div> <div>● Line 6 Grey</div> <div>○ White</div> <div>○ White</div> <div>● Line 3 Blue</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>
<b>Power</b>	Regular power, LED components
<b>Dimensions</b>	Size 1: Varies (w) x 500 mm (h) Size 2: Varies (w) x 750 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	TBD



Surface mounted signage – Multi message



Directional – Surface mounted – Multi message  
Elevation  
1:50



Signface  
Detail  
1:25





Surface mounted – Multi message  
Detail  
1:25

## 4.6 Directional

### Freestanding signage

<b>Sign family</b>	Directional																				
<b>Sign type</b>	Freestanding signage																				
<b>Description</b>	Freestanding directional signs are double sided, non-illuminated signs used at stations with center platforms to indicate the station name and to direct customers to decisions along the platform																				
<b>Typeface</b>	Bloor-Yonge, uppercase Swiss 721 BT Medium, upper & lowercase																				
<b>Colours</b>	<table> <tr> <td>Background</td><td>● Black</td></tr> <tr> <td>Line 1</td><td>● Line 1 Yellow</td></tr> <tr> <td>Line 2</td><td>● Line 2 Green</td></tr> <tr> <td>Line 3</td><td>● Line 3 Blue</td></tr> <tr> <td>Line 4</td><td>● Line 4 Purple</td></tr> <tr> <td>Line 5</td><td>● Line 5 Orange</td></tr> <tr> <td>Line 6</td><td>● Line 6 Grey</td></tr> <tr> <td>Pictograms</td><td>○ White</td></tr> <tr> <td>Text</td><td>○ White</td></tr> <tr> <td>Accessibility</td><td>● Line 3 Blue</td></tr> </table>	Background	● Black	Line 1	● Line 1 Yellow	Line 2	● Line 2 Green	Line 3	● Line 3 Blue	Line 4	● Line 4 Purple	Line 5	● Line 5 Orange	Line 6	● Line 6 Grey	Pictograms	○ White	Text	○ White	Accessibility	● Line 3 Blue
Background	● Black																				
Line 1	● Line 1 Yellow																				
Line 2	● Line 2 Green																				
Line 3	● Line 3 Blue																				
Line 4	● Line 4 Purple																				
Line 5	● Line 5 Orange																				
Line 6	● Line 6 Grey																				
Pictograms	○ White																				
Text	○ White																				
Accessibility	● Line 3 Blue																				
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>																				
<b>Power</b>	Regular power, LED components																				
<b>Dimensions</b>	Varies (w) x 700 mm (h)																				
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>																				
<b>Standard Drawing Detail</b>	S10434.18																				

Freestanding signage




## 4.6 Directional

### Platform identification

Sign family	Directional		
Sign type	Platform identification		
Description	Surface mounted signage placed at platform arrival point		
Typeface	Swiss 721 BT Medium, upper & lowercase		
Colours	Background	●	Black
	Line 1	●	Line 1 Yellow
	Line 2	●	Line 2 Green
	Line 3	●	Line 3 Blue
	Line 4	●	Line 4 Purple
	Line 5	●	Line 5 Orange
	Line 6	●	Line 6 Grey
	Pictograms	○	White
Text	○	White	
Materials	- 4.5mm polycarbonate panels, non-glare, clear - Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films		
Power	Regular power, LED components		
Dimensions	1300 mm (w) x 300 mm (h)		
Fabrication	- Signcomp Series 7 framing components, painted black - Mechanical fastening to suit available structural/surface conditions		
Standard Drawing Detail	TBD		


Platform identification



Directional – Platform identification  
1:50  
Elevation



Platform identification  
1:25  
Detail



Platform identification  
1:25  
Detail


**Design notes:**  
The line number is placed on the side closest to the subway track

## 4.6 Directional

### Next station destination – Surface mounted

<b>Sign family</b>	Directional
<b>Sign type</b>	Next station destination – Surface mounted
<b>Description</b>	Wall mounted signage placed on track side of station
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>Line 1</div> <div>Line 2</div> <div>Line 3</div> <div>Line 4</div> <div>Line 5</div> <div>Line 6</div> <div>Pictograms</div> <div>Text</div> </div> <div> <div>● Black</div> <div>● Line 1 Yellow</div> <div>● Line 2 Green</div> <div>● Line 3 Blue</div> <div>● Line 4 Purple</div> <div>● Line 5 Orange</div> <div>● Line 6 Grey</div> <div>○ White</div> <div>○ White</div> </div>
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced
<b>Power</b>	N/A
<b>Dimensions</b>	1800 mm (w) x 300 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Install signage with mechanical fasteners</li> </ul>
<b>Standard Drawing Detail</b>	SD101437.01

Next station destination – Surface mounted



Directional – Destination signage  
Elevation  
1:100



Destination signage  
Detail  
1:20



Destination signage  
Detail  
1:20


## 4.6 Directional

### Next station destination – Freestanding

<b>Sign family</b>	Directional
<b>Sign type</b>	Next station destination – Freestanding
<b>Description</b>	Freestanding signage placed on track side of station
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div>Background</div> <div>Line 1</div> <div>Line 2</div> <div>Line 3</div> <div>Line 4</div> <div>Line 5</div> <div>Line 6</div> <div>Pictograms</div> <div>Text</div> </div> <div> <div>● Black</div> <div>● Line 1 Yellow</div> <div>● Line 2 Green</div> <div>● Line 3 Blue</div> <div>● Line 4 Purple</div> <div>● Line 5 Orange</div> <div>● Line 6 Grey</div> <div>○ White</div> <div>○ White</div> </div>
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced
<b>Power</b>	N/A
<b>Dimensions</b>	1800 (w) x 300 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 3 framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Standard Drawing Detail</b>	SD101437.01 S10434.18



Next station destination – Freestanding



Directional – Destination signage – Freestanding  
Elevation  
1:100



Destination signage  
Detail  
1:20



Destination signage  
Detail  
1:20

## 4.7 Elevator

### Elevator identification

<b>Sign family</b>	Elevator																				
<b>Sign type</b>	Elevator identification																				
<b>Description</b>	Framed, illuminated sign placed above elevators that identifies elevator destination points																				
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase																				
<b>Colours</b>	<table> <tr> <td>Background</td><td>● Black</td></tr> <tr> <td>Line 1</td><td>● Line 1 Yellow</td></tr> <tr> <td>Line 2</td><td>● Line 2 Green</td></tr> <tr> <td>Line 3</td><td>● Line 3 Blue</td></tr> <tr> <td>Line 4</td><td>● Line 4 Purple</td></tr> <tr> <td>Line 5</td><td>● Line 5 Orange</td></tr> <tr> <td>Line 6</td><td>● Line 6 Grey</td></tr> <tr> <td>Pictograms</td><td>○ White</td></tr> <tr> <td>Text</td><td>○ White</td></tr> <tr> <td>Accessibility</td><td>● Line 3 Blue</td></tr> </table>	Background	● Black	Line 1	● Line 1 Yellow	Line 2	● Line 2 Green	Line 3	● Line 3 Blue	Line 4	● Line 4 Purple	Line 5	● Line 5 Orange	Line 6	● Line 6 Grey	Pictograms	○ White	Text	○ White	Accessibility	● Line 3 Blue
Background	● Black																				
Line 1	● Line 1 Yellow																				
Line 2	● Line 2 Green																				
Line 3	● Line 3 Blue																				
Line 4	● Line 4 Purple																				
Line 5	● Line 5 Orange																				
Line 6	● Line 6 Grey																				
Pictograms	○ White																				
Text	○ White																				
Accessibility	● Line 3 Blue																				
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 4.5 mm polycarbonate panels, non-glare, clear</li> <li>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</li> </ul>																				
<b>Power</b>	Regular power, LED components																				
<b>Dimensions</b>	300 mm (h) x Width to fit (w)																				
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- Signcomp Series 7 post and framing components, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>																				
<b>Standard Drawing Detail</b>	TBD																				


## Elevator identification




**Elevator – Elevator ID**  
Elevation  
1:50

**Design note:**  
Elevator ID's are specified as width to fit.  
The width is determined by any vertical protruding surfaces (i.e. wall, mullion, etc.)

Sign content is centered on the signface.



**Elevator ID**  
Detail  
1:20



**Elevator ID**  
Detail  
1:20

## 4.7 Elevator


### Numbering tag

<b>Sign family</b>	Elevator	
<b>Sign type</b>	Numbering tag	
<b>Description</b>	Elevator identification decals	
<b>Typeface</b>	Swiss 721 BT Medium, uppercase	
<b>Colours</b>	Text	○ White
	Background	● Black
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-010, white</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> <li>- First surface, direct print graphics and/or text</li> </ul>	
<b>Power</b>	N/A	
<b>Dimensions</b>	150 mm (w) x 50 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Radius outside corners, 5 mm</li> <li>- Apply clear, matte vinyl to white vinyl</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> </ul>	

Numbering tag



Elevator – Numbering tag  
Elevation  
1:50



Numbering tag  
Detail  
1:2




Numbering tag  
Detail  
1:2

## 4.7 Elevator

### Non-tactile directory

<b>Sign family</b>	Elevator	
<b>Sign type</b>	Non-tactile directory	
<b>Description</b>	Surface mounted, non-illuminated sign placed adjacent to the elevator control buttons on the exterior of the elevator	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Text	○ White
	Pictograms	○ White
	Background	● Rich black
	Pictograms	○ White
	Line 1	● Line 1 Yellow
	Line 2	● Line 2 Green
	Line 3	● Line 3 Blue
	Line 4	● Line 4 Purple
	Line 5	● Line 5 Orange
	Line 6	● Line 6 Grey
	Accessibility	● Line 3 Blue
	Level indicator	● TTC Red
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	250 mm (w) x Varies (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Install signage with foam tape and silicone adhesive</li> </ul>	
<b>Standard Drawing Detail</b>	SD101437.01	

## Non-tactile directory




**Elevator – Non-tactile directory**  
Elevation  
1:50


**Design note:**

Non-tactile directories should be placed next to the elevator control buttons. When glazing next to the elevator controls is not available the adjacent wall can be used.

If wall does not allow for 500 mm, center directory on the available space.



**Non-tactile directory**  
Detail  
1:10



**Design note:**

When destinations are accessible via another elevator, use a two line text module with "Transfer to" to indicate a transfer is required


## 4.7 Elevator

### Exterior control buttons

<b>Sign family</b>	Elevator		
<b>Sign type</b>	Exterior control buttons		
<b>Description</b>	Single-sided, non-illuminated, tactile sign placed on a blank metal face plate to control the elevator		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot		
<b>Colours</b>	Text	<input type="radio"/>	White
	Background	<input checked="" type="radio"/>	Rich black
	Braille	<input checked="" type="radio"/>	Rich black
	Tactile pictograms	<input type="radio"/>	White
<b>Materials</b>	1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite		
<b>Power</b>	Regular power		
<b>Dimensions</b>	50 mm (w) x 50 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- Raised tactile components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Raised Braille components to be 0.8 mm thick, rich black, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Full contact, continuous sheet, clear, HP adhesive film attachment to: blank, metal face plate, finished black</li> <li>- Dupar Controls to supply: blank, metal face plate, w/ threaded studs welded to backside of plate</li> <li>- Fasten: w/ nuts to push button pressel</li> <li>- US85 push button, by Dupar Controls</li> <li>- Red polycarbonate bezel illuminates, to show active choice</li> </ul>		
<b>Standard Drawing Detail</b>	TBD		



## Exterior control buttons




Exterior control buttons

**Elevator – Exterior control buttons**

Elevation


1:50



**Exterior buttons**

Detail

1:2



**Exterior buttons**

Detail


1:2

## 4.7 Elevator


### Floor designation tags

<b>Sign family</b>	Elevator										
<b>Sign type</b>	Floor designation tags										
<b>Description</b>	Surface mounted, non-illuminated sign placed adjacent to the elevator control buttons on the exterior of the elevator										
<b>Typeface</b>	Swiss 721 BT Light, uppercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot										
<b>Colours</b>	<table> <tr> <td>Tactile number</td><td>○ White</td></tr> <tr> <td>Tactile alpha</td><td>● Rich black</td></tr> <tr> <td>Background</td><td>● Rich black</td></tr> <tr> <td>Braille</td><td>● Rich black</td></tr> <tr> <td>Tactile pictograms</td><td>○ White</td></tr> </table>	Tactile number	○ White	Tactile alpha	● Rich black	Background	● Rich black	Braille	● Rich black	Tactile pictograms	○ White
Tactile number	○ White										
Tactile alpha	● Rich black										
Background	● Rich black										
Braille	● Rich black										
Tactile pictograms	○ White										
<b>Materials</b>	1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite										
<b>Power</b>	N/A										
<b>Dimensions</b>	80 mm (w) x 120 mm (h)										
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- Raised tactile number components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Raised Braille and tactile alpha components to be 0.8 mm thick, rich black, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> <li>- Radius outside corners, 5 mm</li> </ul>										
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Full contact, continuous sheet, clear, HP adhesive film attachment to surface/substrate</li> </ul>										
<b>Standard Drawing Detail</b>	TBD										


Floor designation tags



Elevator – Floor designation tags  
Elevation  
1:50



Floor designation tags  
Detail  
1:2



Floor designation tags  
Detail  
1:2

## 4.7 Elevator

### Fire safety message

<b>Sign family</b>	Elevator		
<b>Sign type</b>	Fire safety message		
<b>Description</b>	Single-sided, non-illuminated sign placed on the elevator exterior above the assistance intercom		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Text	○	White
	Pictograms	○	White
	Pictograms	●	TTC Red
	Background	●	Rich black
	Background	●	TTC Red
<b>Materials</b>	1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	Two lines: 130 mm (w) x 60 mm (h) Three lines: 130 mm (w) x 90 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Backside to be finished black</li> <li>- Radius outside corners, 5 mm</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> </ul>		
<b>Standard Drawing Detail</b>	SD101437.01		

Fire safety message



Elevator – Fire safety message  
Elevation  
1:50



Fire safety message  
Detail  
1:2



Fire safety message  
Detail  
1:2

## 4.7 Elevator


### Assistance Intercom – Exterior

<b>Sign family</b>	Elevator		
<b>Sign type</b>	Assistance Intercom – Exterior		
<b>Description</b>	Single-sided, non-illuminated, tactile sign placed above the elevator control buttons for passenger assistance		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Light, upper & lowercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot		
<b>Colours</b>	Tactile text Background Text Text Pictograms Background Green border Braille	○ White ● Rich black ○ White ● TTC Red ○ White ● Rich black ● Line 2 Green ● Rich black	
<b>Materials</b>	1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite		
<b>Power</b>	Regular power		
<b>Dimensions</b>	132 mm (w) x 315 mm (h)		
<b>Fabrication</b>	- First surface, digitally printed text, using a multi-layered, CMYK additive printing process - Raised tactile components to be 0.8 mm thick, white, semi-gloss finish - Raised Braille components to be 0.8 mm thick, rich black, semi-gloss finish - Background colour to be printed rich black, over non-glare side of acrylic		
<b>Installation</b>	- Mechanically fastened to pre-cut and drilled matching metal backer panel, w/ welded studs, electronics and components - Screws: 3mm Ø, Stainless Steel, Tamper-Resistant, Spanner Flat Head Machine Screws, w/ 4 Points of Attachment. Colour: Black Paint Finish, to match Face Panel - To be integrated into Interior Elevator Control Panel		
<b>Standard Drawing Detail</b>	TBD		

Assistance Intercom – Exterior



Elevator – Assistance Intercom – Exterior  
Elevation  
1:50



Assistance Intercom – Exterior  
Detail  
1:4


## 4.7 Elevator

### Car position indicator


<b>Sign family</b>	Elevator		
<b>Sign type</b>	Car position indicator		
<b>Description</b>	Single-sided, non-illuminated sign placed inside the elevator cab to the right of the car position indicator lights		
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Text	○	White
	Pictograms	○	White
	Background	●	Rich black
<b>Materials</b>	1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	Size 1: 650 mm (w) Size 2: 530 mm (w)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> </ul>		
<b>Standard Drawing Detail</b>	SD101437.01		




Car position indicator



Elevator – Car position indicator  
Elevation  
1:50



Car position indicator  
Detail  
1:5




Car position indicator  
Detail  
1:5

## 4.7 Elevator


### Tactile directory

<b>Sign family</b>	Elevator								
<b>Sign type</b>	Tactile directory								
<b>Description</b>	Single-sided, non-illuminated, tactile sign placed inside the elevator cab adjacent to the elevator buttons on the glazing								
<b>Typeface</b>	Swiss 721 BT Light, upper & lowercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot								
<b>Colours</b>	<table> <tr> <td>Tactile text</td><td>○ White</td></tr> <tr> <td>Background</td><td>● Rich black</td></tr> <tr> <td>Braille</td><td>● Rich black</td></tr> <tr> <td>Tactile pictograms</td><td>○ White</td></tr> </table>	Tactile text	○ White	Background	● Rich black	Braille	● Rich black	Tactile pictograms	○ White
Tactile text	○ White								
Background	● Rich black								
Braille	● Rich black								
Tactile pictograms	○ White								
<b>Materials</b>	1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite								
<b>Power</b>	N/A								
<b>Dimensions</b>	500 mm (w) x Varies (h)								
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- Raised tactile components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Raised Braille components to be 0.8 mm thick, rich black, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> <li>- Radius outside corners, 10 mm</li> </ul>								
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> </ul>								
<b>Standard Drawing Detail</b>	TBD								


Tactile directory



Elevator – Tactile directory  
Elevation  
1:50



Tactile directory  
Detail  
1:5



Tactile directory  
Detail  
1:5

**Design note:**  
When using descriptors for each level, the first letter will match the floor designation tag.  
Example: “Streetcars” on level one would be “1SC” and “Concourse” would be “2C”

## 4.7 Elevator


### Interior control buttons

<b>Sign family</b>	Elevator								
<b>Sign type</b>	Interior control buttons								
<b>Description</b>	Single-sided, non-illuminated, tactile sign placed on a blank metal face plate to control the elevator								
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot								
<b>Colours</b>	<table> <tr> <td>Tactile text</td><td>○ White</td></tr> <tr> <td>Background</td><td>● Rich black</td></tr> <tr> <td>Braille</td><td>● Rich black</td></tr> <tr> <td>Tactile pictograms</td><td>○ White</td></tr> </table>	Tactile text	○ White	Background	● Rich black	Braille	● Rich black	Tactile pictograms	○ White
Tactile text	○ White								
Background	● Rich black								
Braille	● Rich black								
Tactile pictograms	○ White								
<b>Materials</b>	1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite								
<b>Power</b>	Regular power								
<b>Dimensions</b>	50 mm (w) x 50 mm (h)								
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- Raised tactile components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Raised Braille components to be 0.8 mm thick, rich black, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> </ul>								
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Full contact, continuous sheet, clear, HP adhesive film attachment to: blank, metal face plate, finished black</li> <li>- Dupar Controls to supply: blank, metal face plate, w/ threaded studs welded to backside of plate</li> <li>- Fasten: w/ nuts to push button pressel</li> <li>- US85 push button, by Dupar Controls</li> <li>- Red polycarbonate bezel illuminates, to show active choice</li> </ul>								
<b>Standard Drawing Detail</b>	TBD								


Interior control buttons



Elevator – Interior control buttons  
Elevation  
1:50



Interior buttons  
Detail  
1:2




Interior control buttons  
Detail  
1:2

## 4.7 Elevator


### Assistance Intercom – Interior

<b>Sign family</b>	Elevator	
<b>Sign type</b>	Assistance Intercom – Interior	
<b>Description</b>	Single-sided, non-illuminated, tactile sign placed above the elevator control buttons for passenger assistance	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Light, upper & lowercase Grade 1 Braille - 6 mm cell, w/ 1.5 mm diameter dot	
<b>Colours</b>	Tactile text Background Text Pictograms Background Green border	○ White ○ White ● Rich Black ○ White ● Rich Black ● Line 2 Green
<b>Materials</b>	1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite	
<b>Power</b>	Regular power	
<b>Dimensions</b>	230 mm (w) x 230 mm (h)	
<b>Fabrication</b>	- First surface, digitally printed text, using a multi-layered, CMYK additive printing process - Raised tactile components to be 0.8 mm thick, white, semi-gloss finish - Raised Braille components to be 0.8 mm thick, rich black, semi-gloss finish - Background colour to be printed rich black, over non-glare side of acrylic	
<b>Installation</b>	- Mechanically fastened to pre-cut and drilled matching metal backer panel, w/ welded studs, electronics and components - Screws: 3mm Ø, Stainless Steel, Tamper-Resistant, Spanner Flat Head Machine Screws, w/ 4 Points of Attachment. Colour: Black Paint Finish, to match Face Panel - To be integrated into Interior Elevator Control Panel	
<b>Standard Drawing Detail</b>	TBD	

## Assistance Intercom – Interior



**Elevator – Assistance Intercom**  
Elevation  
1:50




## 4.8 Station platform

### Station name – Track wall

<b>Sign family</b>	Station platform
<b>Sign type</b>	Station name – Track wall
<b>Description</b>	
<b>Typeface</b>	Bloor-Yonge, uppercase
<b>Colours</b>	TBD by station colour scheme
<b>Materials</b>	
<b>Power</b>	N/A
<b>Dimensions</b>	250 mm (h)
<b>Fabrication</b>	
<b>Installation</b>	
<b>Standard Drawing Detail</b>	TBD



Station name – Track wall



Station platform – Station name – Track wall

1:50  
Elevation



**Tile band**  
1:25  
Elevation



**Large station name – 250**  
1:25  
Elevation



**Station descriptor – 100**  
1:25  
Elevation





**Small station name – 100**  
1:25  
Elevation

## 4.8 Station platform

### Station name – Platform wall

<b>Sign family</b>	Station platform
<b>Sign type</b>	Station name – Platform wall
<b>Description</b>	
<b>Typeface</b>	Bloor-Yonge, uppercase
<b>Colours</b>	TBD by station colour scheme
<b>Materials</b>	
<b>Power</b>	N/A
<b>Dimensions</b>	250 mm (h)
<b>Fabrication</b>	
<b>Installation</b>	
<b>Standard Drawing Detail</b>	TBD

Station name – Platform wall




## 4.9 Station


### Waste receptacles

<b>Sign family</b>	Station	
<b>Sign type</b>	Waste receptacles	
<b>Description</b>	Decals on waste receptacles to identify garbage and recycling	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase	
<b>Colours</b>	Text	○ White
	Background	● Black
	Background	● Red
	Background	● Blue
	Pictograms	● Black
<b>Materials</b>	- 3M Controltac IJ180MC-010, white - 3M Scotchcal 8520, clear, matte, overlamine	
<b>Power</b>	N/A	
<b>Dimensions</b>	Side: 280 mm (w) x 190 mm (h) Front: 420 mm (w) x 190 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text to white vinyl - Apply clear, matte vinyl to finished decal	
<b>Installation</b>	- Prepare surface prior to installation	
<b>Standard Drawing Detail</b>	SD12932340 SD12932341 SD12932342 SD12932344 SD12932345 SD12932346 SD12932347 SD12932348 SD12932349 SD12932350 SD12932351 SD129323.52 SD129323.53	


Waste receptacles



Station – Waste receptacle  
Elevation  
1:20



Station – Waste receptacle  
Detail  
1:10





## 4.9 Station

### Public Notice

<b>Sign family</b>	Station		
<b>Sign type</b>	Public Notice		
<b>Description</b>	Single sided, non-illuminated sign placed near the entry point to a station		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	Black
	Background	●	TTC Red
	TTC logo	●	TTC Red
	Text	○	White
<b>Materials</b>	- 1.5 mm Sintra, bright white		
<b>Power</b>	N/A		
<b>Dimensions</b>	510 mm (w) x 710 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Custom snap frames</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>		
<b>Installation</b>	- Install signage in snap frame		
<b>Standard Drawing Detail</b>	TBD		

Public Notice




## 4.9 Station

### Closure posters

<b>Sign family</b>	Station	
<b>Sign type</b>	Closure posters	
<b>Description</b>	Temporary signs used for closures	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Background	● Black
	Background	○ White
	Line 1	● Line 1 Yellow
	Line 2	● Line 2 Green
	Line 3	● Line 3 Blue
	Line 4	● Line 4 Purple
	Line 5	● Line 5 Orange
	Line 6	● Line 6 Grey
	Pictograms	○ White
	Text	○ White
	Accessibility	● Line 3 Blue
	No service	● TTC Red
<b>Materials</b>	- 3 mm coroplast	
<b>Power</b>	N/A	
<b>Dimensions</b>	510 mm (w) x 710 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Custom snap frames</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>	
<b>Installation</b>	- Install signage in snap frame	
<b>Standard Drawing Detail</b>	TBD	




Closure posters



Station - Closure posters  
Elevation  
1:25

**Design note:**  
Closure poster frames are located at all station entrances in the unpaid fare zone and at DWA's at platform level.




Closure posters  
Detail  
1:10

## 4.9 Station


### Public room identification

<b>Sign family</b>	Station	
<b>Sign type</b>	Public room identification	
<b>Description</b>	Single sided, non-illuminated tactile room ID sign for rooms available to the public.	
<b>Typeface</b>	Swiss 721 BT Light, upper & lowercase	
<b>Colours</b>	Tactile text	○ White
	Background	○ White
	Braille	● Rich black
	Tactile pictograms	● Rich black
	Tactile pictograms	○ White
	Background	● Rich black
	Background	● Line 3
<b>Materials</b>	- 1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite	
<b>Power</b>	N/A	
<b>Dimensions</b>	150 mm (w) x 250 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- 5 mm Radius outside corners</li> <li>- Raised tactile components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Raised Braille components to be 0.8 mm thick, rich black, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare door or wall prior to installation</li> <li>- Full contact, continuous sheet, clear, HP adhesive film attachment to surface/substrate</li> </ul>	
<b>Standard Drawing Detail</b>	TBD	

Public room identification



Stations – Public room identification  
Elevation  
1:25




Public room identification  
Detail  
1:5

## 4.9 Station


### Bicycle storage

<b>Sign family</b>	Station		
<b>Sign type</b>	Bicycle storage		
<b>Description</b>	Decal and sign to identify bicycle storage rooms		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	Black
	Background	○	White
	Background	●	City of Toronto
	Text	○	White
	Pictograms	○	White
	Pictograms	●	Black
<b>Materials</b>	<b>Bicycle storage supergraphic</b> - 3M Controltac IJ180MC-010, white - 3M Scotchcal 8520, clear, matte, overlamine  <b>Bicycle storage sign</b> - 1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	Supergraphic: 875 mm (w) x 1750 mm (h) Bicycle storage sign: 300 mm (w) x 520 mm (h)		
<b>Fabrication</b>	<b>Bicycle storage supergraphic</b> - Apply clear, matte vinyl to white vinyl - First surface, cut vinyl graphics  <b>Bicycle storage sign</b> - First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes - Black vinyl backer		
<b>Installation</b>	<b>Bicycle storage supergraphic</b> - Prepare surface prior to installation  <b>Bicycle storage sign</b> - Prepare surface prior to installation - Double-sided, HP adhesive foam tape and silicone attachment to surface; or mechanical fastening to suit available structural/surface conditions - Black vinyl backer		
<b>Standard Drawing Detail</b>	SD101437.01		

Bicycle storage



Station - Bicycle storage  
Elevation  
1:100



Bicycle storage supergraphic  
Detail  
1:25




Bicycle storage sign  
Detail  
1:10

## 4.9 Station


### Bicycle repair station

<b>Sign family</b>	Station		
<b>Sign type</b>	Bicycle repair station		
<b>Description</b>	Decals and signs to identify bicycle repair tools		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	Black
	Background	○	White
	Background	●	Red
	Text	○	White
	Pictograms	○	White
	Pictograms	●	Black
<b>Materials</b>	<b>Decal</b> - 3M Controltac IJ180MC-010, white - 3M Scotchcal 8520, clear, matte, overlamine  <b>Sign</b> - 1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	Wheel stand: 55 mm (w) x 75 mm (h) Toolbox: 255 mm (w) x 330 mm (h) Airpump: 55 mm (w) x 75 mm (h) Stand: 80 mm (w) x 190 mm (h) Bicycle repair stop: 300 mm (w) x 520 mm (h)		
<b>Fabrication</b>	<b>Decal</b> - First surface, direct print graphics and/or text to white vinyl - Apply clear, matte vinyl to printed side of vinyl  <b>Sign</b> - First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes		
<b>Installation</b>	<b>Sign</b> - Clean and prepare surface prior to installation - Double-sided, HP adhesive foam tape and silicone attachment to surface; or mechanical fastening to suit available structural/surface conditions; or mechanical fastening to telestrut post		
<b>Standard Drawing Detail</b>	SD101437.01		

Bicycle repair station




Station – Bicycle repair station  
Elevation  
1:50




Wheel stand – Decal  
Detail  
1:2




Air pump – Decal  
Detail  
1:2



Toolbox – Decal  
Detail  
1:10



Bike stand – Decal  
Detail  
1:5



Bicycle repair stop – Sign  
Detail  
1:10


## 4.9 Station

### Bicycle parking


<b>Sign family</b>	Station		
<b>Sign type</b>	Bicycle parking		
<b>Description</b>	Signage to identify bicycle parking		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Background	●	Black
	Background	○	White
	Background	●	Safety Blue
	Text	○	White
	Pictograms	●	Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	Vertical: 300 mm (w) x 520 mm (h) Horizontal: 500 mm (w) x 200 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface; or mechanical fastening to suit available structural/surface conditions; or mechanical fastening to telestrut post</li> </ul>		
<b>Standard Drawing Detail</b>	SD101437.01		




Bicycle parking



Station – Bicycle parking  
Elevation  
1:50






















Bicycle parking – Vertical  
Detail  
1:10



Bicycle parking – Horizontal  
Detail  
1:10

## 4.9 Station

### On-street directional

<b>Sign family</b>	Station
<b>Sign type</b>	On-street directional
<b>Description</b>	Signage directing vehicular traffic to passenger pick-up, parking, etc.
<b>Typeface</b>	Bloor Yonge, uppercase Swiss 721 BT Medium, upper & lowercase
<b>Colours</b>	<div> <div> TTC logo GO Logo YRT Logo UP Logo VIA Logo ZUM Logo MiWay Logo Durham Logo Background Background Line 1 Line 2 Line 3 Line 4 Line 5 Line 6 Pictograms Text Accessibility </div> <div>  TTC Red   GO   YRT   UP   VIA   Züm   MiWay   Durham   Black   White   Line 1 Yellow   Line 2 Green   Line 3 Blue   Line 4 Purple   Line 5 Orange   Line 6 Grey   White   White   Line 3 Blue </div> </div>
<b>Materials</b>	- 3 mm DiBond - Non-glare overlamine
<b>Power</b>	N/A
<b>Dimensions</b>	1200 mm (w) x Varies (h)
<b>Fabrication</b>	- Digitally printed to substrate - Signcomp Series 7 post and framing components, painted black - Mechanical fastening to suit available structural/surface conditions
<b>Standard Drawing Detail</b>	TBD

On-street directional



Station – On-street directional  
Elevation  
1:25



On-street directional  
Detail  
1:10

## 4.9 Station

### Crisis Link poster


<b>Sign family</b>	Station
<b>Sign type</b>	Crisis Link poster
<b>Description</b>	Single sided, non-illuminated sign placed on the oncoming train end of platforms on the wall next to the blue light or adjacent wall
<b>Typeface</b>	N/A
<b>Colours</b>	N/A
<b>Materials</b>	- 1.5 mm Sintra, bright white
<b>Power</b>	N/A
<b>Dimensions</b>	510 mm (w) x 710 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Custom snap frames, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Installation</b>	- Install signage in snap frame
<b>Standard Drawing Detail</b>	TBD

Crisis Link poster



Station – Crisis Link poster  
Elevation  
1:25





**Design note:**  
Crisis Link poster frames are located at the end of each platform at the tunnel entrance where trains enter the station.



Crisis Link poster  
Detail  
1:10

## 4.9 Station


### Emergency alarm station – Platform

<b>Sign family</b>	Station		
<b>Sign type</b>	Emergency alarm station – Platform		
<b>Description</b>	Single sided, non-illuminated numeric sign located at platform level		
<b>Typeface</b>	Swiss 721 BT Bold, uppercase		
<b>Colours</b>	Text		White
	Pictograms		White
	Background		TTC Red
	Background		Black
<b>Materials</b>	- 3M Controltac IJ180MC-010, white - 3M Scotchcal 8520, clear, matte, overlamine		
<b>Power</b>	N/A		
<b>Dimensions</b>	75 mm (w) x 25 mm (h)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text to white vinyl - Apply clear, matte vinyl to white vinyl		
<b>Installation</b>	- Clean and prepare surface prior to installation - Ensure there are no bubbles		


Emergency alarm station – Platform



Platform – Emergency alarm station  
Detail  
1:10



EAS decal  
Detail  
1:5



ET-Phone Location decal  
Detail  
1:5



Phone ID decal  
Detail  
1:5


## 4.9 Station

### Platform end gate

<b>Sign family</b>	Station	
<b>Sign type</b>	Platform end gate	
<b>Description</b>	Single sided, non-illuminated safety sign located on platform end gate	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Danger Caution Prohibited Text Pictograms Background Notice	● TTC Red ● Safety Yellow ● TTC Red ○ White ○ White ● Black ● Safety Blue
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	350 mm (w) x 570 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes	
<b>Installation</b>	- Clean and prepare surface prior to installation - Install using 4 points of attachment using mechanical fasteners	
<b>Standard Drawing Detail</b>	SD101437.01	



Platform end gate



Platform level – Platform end gate  
Elevation  
1:25



Platform level – Public side  
Detail  
1:10



Platform level – Track – Left  
Detail  
1:10




Platform level – Track – Right  
Detail  
1:10

## 4.10 Maps

### You are here

<b>Sign family</b>	Maps
<b>Sign type</b>	You are here
<b>Description</b>	Single-sided, non-illuminated map located on subway platforms that shows customers "You are Here" and what stops are available on the current platform
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>Background</div> <div>● Black</div> <div>Background</div> <div>○ White</div> <div>Line 1</div> <div>● Line 1 Yellow</div> <div>Line 2</div> <div>● Line 2 Green</div> <div>Line 3</div> <div>● Line 3 Blue</div> <div>Line 4</div> <div>● Line 4 Purple</div> <div>Line 5</div> <div>● Line 5 Orange</div> <div>Line 6</div> <div>● Line 6 Grey</div> <div>Pictograms</div> <div>○ White</div> <div>Text</div> <div>○ White</div> <div>Accessibility</div> <div>● Line 3 Blue</div> <div>You are here</div> <div>● TTC Red</div> </div>
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 1.5 mm Sintra, bright white</li> <li>- First surface, direct print graphics and/or text</li> </ul>
<b>Power</b>	N/A
<b>Dimensions</b>	510 mm (w) x 710 mm (h)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Custom snap frames, painted black</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Install signage in snap frame</li> </ul>
<b>Standard Drawing Detail</b>	TBD

You are here




Maps – You Are Here (YAH)  
Elevation  
1:25

510

**Design note:**  
You Are Here (YAH) maps are placed at decision points between concourse and side platforms. Typically these are placed at stairs and escalators.

YAH maps are placed at arrival points at centre platforms.

If surfaces are not available, a freestanding frame should be used.




Maps – You Are Here (YAH)  
Detail  
1:10

## 4.11 Track level signage

### Public safety – Refuge cage

<b>Sign family</b>	Track level signage	
<b>Sign type</b>	Public safety – Refuge cage	
<b>Description</b>	Single sided, non-illuminated safety signs located on refuge cages	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Danger Caution Prohibited Text Pictograms Background Notice	● TTC Red ● Safety Yellow ● TTC Red ○ White ● Black ● Black ● Safety Blue
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	Mind the Gap: 300 mm (w) x 520 mm (h) Stand Back: 300 mm (w) x 520 mm (h) High Voltage: 900 mm (w) x 300 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes	
<b>Installation</b>	- Clean and prepare surface prior to installation - Mechanical fastening to suit available structural/surface conditions - Double-sided, HP adhesive foam tape and silicone attachment to surface	
<b>Standard Drawing Detail</b>	SD101437.01	

Public safety – Refuge cage



Track level – Metal and mesh refuge cages  
Elevation  
1:50




## 4.11 Track level signage

### Public safety – Refuge cage

<b>Sign family</b>	Track level signage	
<b>Sign type</b>	Public safety – Refuge cage	
<b>Description</b>	Single sided, non-illuminated safety signs located on refuge cages	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Danger Caution Prohibited Text Pictograms Background Notice	● TTC Red ● Safety Yellow ● TTC Red ○ White ● Black ● Black ● Safety Blue
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	Mind the Gap: 300 mm (w) x 520 mm (h) Stand Back: 300 mm (w) x 520 mm (h) High Voltage: 900 mm (w) x 300 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes	
<b>Installation</b>	- Clean and prepare surface prior to installation - Mechanical fastening to suit available structural/surface conditions - Double-sided, HP adhesive foam tape and silicone attachment to surface	
<b>Standard Drawing Detail</b>	SD101437.01	

Public safety – Refuge cage



Track level – Stainless steel refuge cages  
Elevation  
1:50



Mind the gap  
Detail  
1:10

Stand back  
Detail  
1:10

High voltage  
Detail  
1:20


## 4.11 Track level signage

### Public safety – Track wall


<b>Sign family</b>	Track level signage	
<b>Sign type</b>	Public safety – Track wall	
<b>Description</b>	Single sided, non-illuminated safety signs located on refuge cages	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Danger Caution Prohibited Text Pictograms Background Notice	● TTC Red ● Safety Yellow ● TTC Red ○ White ● Black ● Black ● Safety Blue
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	Mind the Gap: 300 mm (w) x 520 mm (h) Stand Back: 300 mm (w) x 520 mm (h) High Voltage: 900 mm (w) x 300 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes	
<b>Installation</b>	- Clean and prepare surface prior to installation - Double-sided, HP adhesive foam tape and silicone attachment to surface	
<b>Standard Drawing Detail</b>	SD101437.01	



Public safety – Track wall



Track level – Surface mounted  
Elevation  
1:100





## 4.11 Track level signage

### Chainage markers

<b>Sign family</b>	Track level signage		
<b>Sign type</b>	Platform end gate		
<b>Description</b>	Single sided, non-illuminated numeric sign located at track level		
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase		
<b>Colours</b>	Text	○	White
	Background	●	Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	500 mm (w) x 140 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>		
<b>Standard Drawing Detail</b>	SD101437.01		

Chainage markers




## 4.11 Track level signage

### Emergency alarm station – Track

<b>Sign family</b>	Track level signage	
<b>Sign type</b>	Emergency alarm station – Track	
<b>Description</b>	Single sided, non-illuminated decals located at track level EASs	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase Swiss 721 BT Black Condensed, uppercase	
<b>Colours</b>	Text Pictograms Background Background Line 1 Line 2 Line 3 Line 4 Line 5 Line 6	○ White ○ White ● TTC Red ● Black ● Line 1 Yellow ● Line 2 Green ● Line 3 Blue ● Line 4 Purple ● Line 5 Orange ● Line 6 Grey
<b>Materials</b>	- 3M Controltac IJ180MC-010, white - 3M Scotchcal 8520, clear, matte, overlamine	
<b>Power</b>	N/A	
<b>Dimensions</b>	Phone ID decal: 100 mm (w) x 80 mm (h) ET number decal: 90 mm (w) x 45 mm (h) Press decal: 90 mm (w) x 40 mm (h) PAX location decal: 150 mm (w) x 100 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text to white vinyl - Apply clear, matte vinyl to white vinyl - Radius outside corners, 5 mm	
<b>Installation</b>	- Clean and prepare surface prior to installation - Ensure there are no bubbles	

Emergency alarm station – Track





## 4.11 Track level signage

### Trip distance markers

<b>Sign family</b>	Track level signage	
<b>Sign type</b>	Trip distance markers	
<b>Description</b>	Single sided, non-illuminated sign located above the Emergency Power Cut (EPC) unit	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase	
<b>Colours</b>	Arrow Text Background Background Background Text	○ White ○ White ● Location trip green ● Safety yellow ● Black ● Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	One direction: 700 mm (w) x 140 mm (h) Two directions: 1260 mm (w) x 140 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes	
<b>Installation</b>	- Clean and prepare surface prior to installation - Mechanical fastening to suit available structural/surface conditions; or mechanical fastening to telestrut post	
<b>Standard Drawing Detail</b>	SD101437.01	

Trip distance markers




## 4.11 Track level signage

### Dry drop ID


<b>Sign family</b>	Track level signage		
<b>Sign type</b>	Dry drop ID		
<b>Description</b>	Single sided, non-illuminated sign located above the Dry Drop		
<b>Typeface</b>	Swiss 721 BT Bold, uppercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	Text	●	Black
	TTC Logo	●	TTC Red
	Background	●	TTC Red
	Background	○	White
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	250 mm (w) x 250 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>		
<b>Standard Drawing Detail</b>	SD101437.01		



Dry drop ID



Track level – Dry drop ID  
Elevation  
1:50



Dry drop ID  
Detail  
1:10

## 4.12 Street level signage


### Emergency Exit Building

<b>Sign family</b>	Street level signage	
<b>Sign type</b>	Emergency Exit Building	
<b>Description</b>	Single sided, non-illuminated sign for emergency exit building name	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Background Text	<ul style="list-style-type: none"> <li>● Black</li> <li>○ White</li> </ul>
<b>Materials</b>	<p><b>Emergency Exit Building – ID</b> - 3 mm Dibond panels, black, by Alusuisse Composites Inc.</p> <p><b>Municipal address</b> Designer may elect to fabricate with materials to compliment architectural finishes</p>	
<b>Power</b>	N/A	
<b>Dimensions</b>	<p>EEB ID: 300 mm (h)</p> <p>Municipal address: 250 mm (h)</p>	
<b>Fabrication</b>	<p><b>Emergency Exit Building – ID</b> - First surface, direct print graphics and/or text - Signcomp Series 7 post and framing components, painted black - Mechanical fastening to suit available structural/surface conditions</p> <p><b>Municipal address</b> Designer may elect to fabricate with materials to compliment architectural finishes</p>	
<b>Standard Drawing Detail</b>	SD101423.09	


Emergency Exit Building



Emergency Exit Building – ID  
Front elevation  
1:50



Emergency Exit Building – Municipal address  
Side elevation  
1:50




4.13 Safety and security

Designated waiting area


Sign family	Safety and security		
Sign type	Designated waiting area		
Description	Double sided, illuminated sign for designated waiting areas		
Typeface	Swiss 721 BT Bold, upper & lowercase		
Colours	Text	<input type="radio"/>	White
	Background	<input checked="" type="radio"/>	Black
Materials	<div>- 4.5mm polycarbonate panels, non-glare, clear</div> <div>- Second surface vinyl graphics and/or text, using 3M 3630 Series, Scotchcal Translucent Graphic Films</div>		
Power	Regular power, LED components		
Dimensions	1200 mm (w) x 250–400 mm (h)		
Fabrication	<div>- Signcomp Series 7 post and framing components, painted black</div> <div>- Mechanical fastening to suit available structural/surface conditions</div>		
Installation			

Standard Drawing Detail	SD101423.01
	SD101423.02
	SD101423.03
	SD101423.04
	SD101423.05
	SD101423.06
	SD101423.07
	SD101423.08

## Designated waiting area



**Safety - Designated waiting area**  
Elevation  
1:50




**Designated waiting area**  
Detail  
1:10

## 4.13 Safety and security

### Property control


<b>Sign family</b>	Safety and security	
<b>Sign type</b>	Property control	
<b>Description</b>	Single sided, non-illuminated safety signs located at surface platforms	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Danger Caution Prohibited Text Pictograms Background	● TTC Red ● Safety Yellow ● TTC Red ○ White ● Black ● Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	Fence: 1050 mm (w) x 300 mm (h) Wall: 600 mm (w) x 600 mm (h)	
<b>Fabrication</b>	- First surface, direct print graphics and/or text - Radius outside corners, 5 mm - Backside to be finished black - Powdercoat finishes	
<b>Installation</b>	- Clean and prepare surface prior to installation - Double-sided, HP adhesive foam tape and silicone attachment to surface - Mechanical fastening to suit available structural/surface conditions	
<b>Standard Drawing Detail</b>	SD101437.01	

Property control



Safety – Property control – Fence  
Elevation  
1:50

Safety – Property control – Surface  
Elevation  
1:50



Danger – Moving Vehicles – Fence  
Detail  
1:20



Danger – Moving Vehicles – Surface  
Detail  
1:20


## 4.13 Safety and security

### Emergency and evacuation – Station

<b>Sign family</b>	Safety and security	
<b>Sign type</b>	Emergency and evacuation – Station	
<b>Description</b>	Single sided, non-illuminated safety signs located in subway stations	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Background	● Safety Instruction Green
	Background	○ White
	Background	● Black
	Text	○ White
	Pictograms	● TTC Red
	Pictograms	● Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	250 mm (w) x 450 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>	
<b>Standard Drawing Detail</b>	SD101437.01	




Emergency and evacuation – Station



Safety – Emergency and evacuation – Station  
Elevation  
1:50

**Design note:**  
A minimum of one emergency sign must be placed per level or per instructions by TTC Fire and Safety.  
  
Coordinate locations with TTC Fire and Safety and TTC Design and Wayfinding.




Emergency and evacuation – Station  
Detail  
1:5

## 4.13 Safety and security

### Emergency and evacuation – Facility

<b>Sign family</b>	Safety and security	
<b>Sign type</b>	Emergency and evacuation – Facility	
<b>Description</b>	Single sided, non-illuminated safety signs located in TTC facilities	
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Background	● Safety Instruction Green
	Background	○ White
	Background	● Black
	Text	○ White
	Pictograms	● TTC Red
	Pictograms	● Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	250 mm (w) x 500 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> <li>- Mechanical fastening to suit available structural/surface conditions</li> </ul>	
<b>Standard Drawing Detail</b>	SD101437.01	


Emergency and evacuation – Facility



Safety – Emergency and evacuation – Facility  
Elevation  
1:50

**Design note:**  
A minimum of one emergency sign must be placed per level or per instructions by TTC Fire and Safety.

Coordinate locations with TTC Fire and Safety and TTC Design and Wayfinding.




Emergency and evacuation – Facility  
Detail  
1:5

## 4.13 Safety and security


### Operator indicator dots

<b>Sign family</b>	Safety and security
<b>Sign type</b>	Operator indicator dots
<b>Description</b>	Single sided, non-illuminated sign for train operation
<b>Typeface</b>	N/A
<b>Colours</b>	<div> <div>Train stop - Driver</div> <div>●</div> <div>Train stop red</div> </div> <div> <div>Train stop - Warning</div> <div>●</div> <div>Train stop orange</div> </div> <div> <div>Train stop - Guard</div> <div>●</div> <div>Train stop green</div> </div>
<b>Materials</b>	- 1.5 mm aluminum panels, pan faced
<b>Power</b>	N/A
<b>Dimensions</b>	200 mm (diameter)
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare surface prior to installation</li> <li>- Double-sided, adhesive foam tape attachment to cut MDF backer</li> </ul>
<b>Standard Drawing Detail</b>	SD101437.01


## Operator indicator dots




Train Stop – Driver  
Size: Diameter 200 mm



Train Stop – Warning  
Size: Diameter 200 mm



Train Stop – Guard  
Size: Diameter 200mm




## 4.14 Back of house


### Room identification – Signage

<b>Sign family</b>	Back of house	
<b>Sign type</b>	Room identification – Signage	
<b>Description</b>	Surface mounted, single sided, non-illuminated sign located on service room doors at transit station and other TTC properties	
<b>Typeface</b>	Swiss 721 BT Medium, upper & lowercase	
<b>Colours</b>	Text	○ White
	Pictograms	○ White
	Background	○ White
	Accessibility	● Line 3 Blue
	Pictograms	● Black
	Background	● Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	150 mm (w) x 225 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare door or wall prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> <li>- For fenced doors install signage with mechanical fasteners</li> </ul>	
<b>Standard Drawing Detail</b>	SD101437.01	

Room identification – Signage



Back of house – Room identification  
Elevation  
1:25



Room identification  
Detail  
1:5


## 4.14 Back of house

### Room identification

<b>Sign family</b>	Back of house										
<b>Sign type</b>	Emergency stairwell identification										
<b>Description</b>	Single sided, non-illuminated tactile sign on fire stairwell doors (or adjacent walls) and identifies the stairwell and floor number at TTC properties.										
<b>Typeface</b>	Swiss 721 BT Bold, upper & lowercase Swiss 721 BT Medium, upper & lowercase										
<b>Colours</b>	<table> <tr> <td>Tactile text</td><td>○ White</td></tr> <tr> <td>Background</td><td>○ White</td></tr> <tr> <td>Text</td><td>● Rich black</td></tr> <tr> <td>Pictograms</td><td>● Rich black</td></tr> <tr> <td>Background</td><td>● Rich black</td></tr> </table>	Tactile text	○ White	Background	○ White	Text	● Rich black	Pictograms	● Rich black	Background	● Rich black
Tactile text	○ White										
Background	○ White										
Text	● Rich black										
Pictograms	● Rich black										
Background	● Rich black										
<b>Materials</b>	<p><b>Stairwell identification</b></p> <ul style="list-style-type: none"> <li>- 1.5 mm acrylic panels, non-glare, heavy matte finish, black, by Plaskolite</li> </ul> <p><b>Track entry doors</b></p> <ul style="list-style-type: none"> <li>- 1.5 mm aluminum panels, flat faced</li> </ul>										
<b>Power</b>	N/A										
<b>Dimensions</b>	150 mm (w) x 225 mm (h) 500 mm (w) x 400 mm (h)										
<b>Fabrication</b>	<p><b>Stairwell identification</b></p> <ul style="list-style-type: none"> <li>- First surface, digitally printed text, using a multi-layered, CMYK additive printing process</li> <li>- 5 mm Radius outside corners</li> <li>- Raised tactile components to be 0.8 mm thick, white, semi-gloss finish</li> <li>- Background colour to be printed rich black, over non-glare side of acrylic</li> </ul> <p><b>Track entry doors</b></p> <ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>										
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare door or wall prior to installation</li> <li>- Full contact, continuous sheet, clear, HP adhesive film attachment to surface/substrate</li> </ul>										
<b>Standard Drawing Detail</b>	TBD										



Room identification



Back of house – Stairwell identification  
Elevation  
1:25



Stairwell identification  
Detail  
1:5


Track entry doors  
Detail  
1:10

## 4.14 Back of house


### Fire door – Decals

<b>Sign family</b>	Back of house		
<b>Sign type</b>	Fire door – Decals		
<b>Description</b>	Coloured decal on door to indicate a fire door		
<b>Typeface</b>	Swiss 721 BT Bold, uppercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	White Red	○ White ● TTC Red	
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-010, white</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> <li>- 3M 180MC-10, black underlamine</li> </ul>		
<b>Power</b>	N/A		
<b>Dimensions</b>	600 mm (w) x 100 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply clear, matte vinyl to white vinyl</li> <li>- Apply decal to black underlamine</li> <li>- Radius outside corners, 5 mm</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Ensure there are no bubbles</li> </ul>		

Fire door – Decals



Back of house – Fire door decals  
Elevation  
1:25




Fire door  
Detail  
1:10

## 4.14 Back of house


### Fire door – Decals

<b>Sign family</b>	Back of house		
<b>Sign type</b>	Fire door – Decals		
<b>Description</b>	Coloured decal on door to indicate a fire door		
<b>Typeface</b>	Swiss 721 BT Bold, uppercase Swiss 721 BT Medium, upper & lowercase		
<b>Colours</b>	White Red	○ White ● TTC Red	
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-010, white</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>		
<b>Power</b>	N/A		
<b>Dimensions</b>	600 mm (w) x 100 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text to white vinyl</li> <li>- Apply clear, matte vinyl to white vinyl</li> <li>- Radius outside corners, 5 mm</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare surface prior to installation</li> <li>- Ensure there are no bubbles</li> </ul>		

Fire door – Decals







Back of house – Fire door decals  
Elevation  
1:25




Fire door  
Detail  
1:10

## 4.15 Front of house


### Room ID – Door decals

<b>Sign family</b>	Front of house		
<b>Sign type</b>	Room ID – Door decals		
<b>Description</b>	Coloured decal on door for staff washroom, janitor utility room or service rooms		
<b>Typeface</b>	N/A		
<b>Colours</b>	Male staff		Staff men washroom
	Female staff		Staff female washroom
	Janitor utility		Janitor purple
	Safety yellow		Safety yellow
	Black		Black
<b>Materials</b>	- 3M Controltac IJ180MC-010, white - 3M Scotchcal 8520, clear, matte, overlamine		
<b>Power</b>	N/A		
<b>Dimensions</b>	50 mm (diameter)		
<b>Fabrication</b>	- First surface, direct print graphics and/or text to white vinyl - Apply clear, matte vinyl to white vinyl		
<b>Installation</b>	- Clean and prepare door surface prior to installation - For double-doors, install decals on door with latch - For exterior doors that lead to rooms beyond, decal groups are required		

Room ID – Door decals



Room ID – Door decals  
Elevation  
1:25




## 4.15 Front of house

### Equipment ID – Door decals

<b>Sign family</b>	Front of house		
<b>Sign type</b>	Equipment ID – Door decals		
<b>Description</b>	Coloured decal on door for equipment in room		
<b>Typeface</b>	N/A		
<b>Colours</b>	White Green Blue	<div>○ White</div> <div>● Safety Instructions Green</div> <div>● Safety Partner Blue</div>	
<b>Materials</b>	- 3M-680-10 White		
<b>Power</b>	N/A		
<b>Dimensions</b>	50 mm (diameter)		
<b>Fabrication</b>	- Digital print to 3M reflective vinyl		
<b>Installation</b>	- Prepare door surface prior to installation - For double-doors, install decals on door with latch		




Equipment ID – Door decals



Equipment ID – Room decals  
Elevation  
1:25



Permanent Work Area Warning  
Detail  
1:2



First Aid Rm  
Detail  
1:2



AED Equip Rm  
Detail  
1:2

Eyewash Equip Rm  
Detail  
1:2


Shower Equip Rm  
Detail  
1:2

## 4.15 Front of house

### Emergency services ID – Door decals

<b>Sign family</b>	Front of house	
<b>Sign type</b>	Emergency services ID – Door decals	
<b>Description</b>	Coloured decal on door for emergency services	
<b>Typeface</b>	N/A	
<b>Colours</b>	White Red	 White  TTC Red
<b>Materials</b>	- 3M-680-10 White	
<b>Power</b>	N/A	
<b>Dimensions</b>	50 mm (diameter)	
<b>Fabrication</b>	- Digital print to 3M reflective vinyl	
<b>Installation</b>	- Prepare door surface prior to installation - For double-doors, install decals on door with latch	

Emergency services ID – Door decals



Emergency services ID – Door decals  
Elevation  
1:25




## 4.15 Front of house

### Door numbering

<b>Sign family</b>	Front of house		
<b>Sign type</b>	Door numbering		
<b>Description</b>	Single sided, non-illuminated alphanumeric sign located at the top of doors that identifies the door number at transit stations and other TTC properties		
<b>Typeface</b>	Swiss 721 BT Medium, Uppercase		
<b>Colours</b>	Text	○	White
	Background	●	Black
<b>Materials</b>	<ul style="list-style-type: none"> <li>- 3M Controltac IJ180MC-010, white</li> <li>- 3M Scotchcal 8520, clear, matte, overlamine</li> </ul>		
<b>Power</b>	N/A		
<b>Dimensions</b>	150 mm (w) x 75 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare door surface prior to installation</li> </ul>		

Door numbering



Front of house – Door numbering  
Elevation  
1:25





Door numbering  
Detail  
1:2

## 4.15 Front of house

### Stair numbering

<b>Sign family</b>	Front of house		
<b>Sign type</b>	Stair numbering		
<b>Description</b>	Single sided, non-illuminated alphanumeric sign located at the top and bottom of the stairwell that identifies the stair number at transit stations and other TTC properties		
<b>Typeface</b>	Swiss 721 BT Medium, Uppercase		
<b>Colours</b>	Text	○	White
	Background	●	Black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced		
<b>Power</b>	N/A		
<b>Dimensions</b>	150 mm (w) x 50 mm (h)		
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>		
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Prepare stairwell surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> </ul>		
<b>Standard Drawing Detail</b>	SD101437.01		

Stair numbering




## 4.15 Front of house

### Escalator numbering

<b>Sign family</b>	Front of house	
<b>Sign type</b>	Escalator numbering	
<b>Description</b>	Single sided, non-illuminated alphanumeric sign located at the top and bottom of the escalator that identifies the stair number at transit stations and other TTC properties	
<b>Typeface</b>	Swiss 721 BT Medium, Uppercase	
<b>Colours</b>	Text	○ White
	Background	● Rich black
<b>Materials</b>	- 1.5 mm aluminum panels, flat faced	
<b>Power</b>	N/A	
<b>Dimensions</b>	150 mm (w) x 50 mm (h)	
<b>Fabrication</b>	<ul style="list-style-type: none"> <li>- First surface, direct print graphics and/or text</li> <li>- Radius outside corners, 5 mm</li> <li>- Backside to be finished black</li> <li>- Powdercoat finishes</li> </ul>	
<b>Installation</b>	<ul style="list-style-type: none"> <li>- Clean and prepare escalator surface prior to installation</li> <li>- Double-sided, HP adhesive foam tape and silicone attachment to surface</li> </ul>	
<b>Standard Drawing Detail</b>	SD101437.01	



Escalator numbering



Front of house – Escalator numbering  
Elevation  
1:25



Escalator numbering  
Detail  
1:2

